

**STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
AIRPORTS DIVISION**

**ADDENDUM NO. 1
TO
SPECIAL PROVISIONS, SPECIFICATIONS, AND PROPOSAL
FOR**

**MAINTENANCE OF ELECTRICAL EQUIPMENT
LIHUE AIRPORT
PROJECT NO. BK1321-53**

OCTOBER 3, 2022

The following is provided for information:

A. RESPONSES TO REQUEST FOR INFORMATION (RFI)


1. Question: Are you able to give us more information on the ATS' and Switchgear?

Response: Yes, information can be found on the attached Electrical Maintenance Testing Report.

B. ELECTRICAL MAINTENANCE TESTING REPORT

1. The attached Electrical Maintenance Testing Report for the Lihue Airport is provided for your information.

Please acknowledge receipt of this Addendum No.1 by recording the date of its receipt in the space provided on page PF-4 of the Proposal.



JADE T. BUTAY
Director of Transportation


EXHIBIT A



Lihue Airport

Electrical Maintenance Testing Report

Report Prepared By Jared Helminen, P.E.





ELECTRO TEST

OAHU, HAWAII



Lihue Airport Electrical Maintenance

Customer: American Electric

Dates of Work Performed: 03/21-03/25/2022

Contact: Clark Tyler

Type of Service: Electrical Maintenance Testing

Summary

Electrical acceptance testing was performed by Electro Test personnel at Lihue Airport and coordinated with airport personnel. While most equipment is in fair working condition there were multiple deficiencies found and they are listed below.

Deficiencies

1. ATS 1 has burnt out bulbs and some corrosion on the mechanical parts. Recommend replacing bulbs and installing heaters.
2. ATS 2 has a bad circuit to the racking solenoid and the switches at the racking mechanism as well as the permissive switch at the Bypass mechanism should be replaced. This unit also has corrosion.
3. Heaters in ATS 1 and ATS 2 are inoperable. (2) New circuits should be pulled to this location and working heaters should be installed to alleviate moisture and corrosion on these units. This will significantly extend the useful life of these units.
4. Insulation resistance readings on all circuit breakers in the Main Switchboard and Generator Switchboard were very low. It is recommended that heaters be installed to prevent further moisture penetration.
5. The Control Tower (Airfield) ATS failed during testing and needs to be replaced. The bypass unit and transfer coil are both failed. This unit is old and has a date code of 02/2001.
6. The ARFF automatic transfer switch failed previous maintenance cycles and still has not been replaced. The mechanical portion of the switch is in very bad condition and could cause safety concerns going forward.



ELECTRO TEST

OAHU, HAWAII



The controller is also faulty so the whole switch assembly must be replaced as soon as possible.

Please see all attached test forms and feel free to contact us with any questions. A quotation will be provided for correcting deficiencies.

Mahalo,

Jared Helminen, P.E.



Lihue Airport Electrical Maintenance – NETA Testing Results TABLE OF CONTENTS

LOW VOLTAGE CIRCUIT BREAKERS.....	1
<i>G1 BREAKER.....</i>	<i>2</i>
<i>G2 BREAKER.....</i>	<i>3</i>
<i>ATS 1 EMERGENCY FEEDER BREAKER</i>	<i>4</i>
<i>ATS 2 EMERGENCY FEEDER BREAKER.....</i>	<i>5</i>
<i>CAPACITOR BREAKER.....</i>	<i>6</i>
<i>MAIN 1 BREAKER.....</i>	<i>7</i>
<i>TIE BREAKER.....</i>	<i>8</i>
<i>MAIN 2 BREAKER.....</i>	<i>9</i>
<i>ATS 1 FEEDER BREAKER.....</i>	<i>10</i>
<i>ATS 2 FEEDER BREAKER.....</i>	<i>11</i>
<i>ATS 4 FEEDER BREAKER.....</i>	<i>12</i>
<i>SBA FEEDER BREAKER.....</i>	<i>13</i>
<i>SBB FEEDER BREAKER.....</i>	<i>14</i>
 AUTOMATIC TRANSFER SWITCHES	 15
<i>ATS 1</i>	<i>16</i>
<i>ATS 2</i>	<i>17</i>
<i>ATS 4</i>	<i>18</i>
<i>MAINTENANCE BASEYARD ATS.....</i>	<i>19</i>
<i>AIRFIELD ATS.....</i>	<i>20</i>
<i>ARFF ATS</i>	<i>21</i>



LOW VOLTAGE CIRCUIT BREAKERS

Insulated Case Circuit Breaker Test and Inspection
G1

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/22/2022	Location Lihue, HI	Equipment Tag ID G1
Manufacturer General Electric	Model Power Break	SERIAL NUMBER AC16367-2
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587, AEMC 6240)	Test Equipment Last Calibration Date 8/20/2020	Substation Primary

Ambient Temperature Humidity Breaker Type Fuse Catalog Number Counter as Found Counter As Left	25 60 GE Power Breaker N/A N/A N/A	°C %	Trip Unit Type Trip Unit Catalog Number Frame Size	MVT+ RMS9C122953 1600	Amps	CAT number Cubicle Code Sensor Taps	THC1616TTEI N/A 1600
Mounting Draw-Out	Thermal Memory ON	ZONE INTERLOCK GF	OFF ON				

Proper Mounting	Inspected	Pass	No Action Needed	Insulating Members	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed	Structural Members	Inspected	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed	Contact Fingers	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed	Arcing Contacts	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed	Arc Chutes	Inspected	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed	Auxiliary Devices	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed	Overcurrent Device Battery	Inspected	Pass	No Action Needed
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed				

Overall Visual Inspection PASSED INSPECTION

Settings as Found	Function	Pickup	Delay
GroundFault 3W	Rating Plug 1600 Long Sensor Tap 1600 Short	1600 A 0 A 1600 A 1600 A	1200 A 0 A 16000 A 320 A
	Instantaneous Ground Fault		1 0 3 Out

Settings as Left	Function	Pickup	Delay
GroundFault 3W	Rating Plug 1600 Long Sensor Tap 1600 Short	1600 A 0 A 1600 A 1600 A	1200 A 0 A 16000 A 320 A
	Instantaneous Ground Fault		1 0 3 Out

Timing Tests						
Trip Curve (TCC) Number GES-9913						
Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds
			Minimum	Maximum		
Long Time	3600	3XIr	8	16	11.42	11.42
Short Time	LTPU (amps)					0
	STPU (amps)					0
Instantaneous	16000	8XIn	0.01	0.07	0.05	0.05
	IPIU (amps)					0
Ground Fault	480	1XIn	0.38	0.5	0.39	0.39
	GFPU (amps)					0

Contact Resistance Across Closed Poles							
Breaker Current Rating	1600	Amps	Phase A	Measurements	Deviation	Deviation	Overall
Maximum Percent Load	100%	%		Phase B	µΩ		
Maximum Load	1600		Phase C	38	8.57%	PASS	PASS
				35	0.00%	PASS	
				49	40.00%	PASS	

Insulation Resistance						
Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature	25	°C	
Minimum Test Voltage	1000	kVDC	Temperature Correction Factor	1.25		
Test Voltage Used	1000	kVDC	Minimum Insulation Resistance	100	MΩ	
Test Duration per Reading	60	Seconds				
State	Points	Measurements	Corrected for °C		Pass or Fail	
Closed	A to B	72	MΩ	90	PASS	
Closed	B to C	50	MΩ	62.5	PASS	
Closed	C to A	70	MΩ	87.5	PASS	
Closed	A to G	65	MΩ	81.25	PASS	
Closed	B to G	52	MΩ	65	PASS	
Closed	C to G	50	MΩ	62.5	PASS	
Open	A Line - Load	185	MΩ	231.25	PASS	
Open	B Line - Load	85	MΩ	106.25	PASS	
Open	C Line - Load	2200	MΩ	2750	PASS	
Any	Control Wiring	2200	MΩ	2750	PASS	

OVERALL PASS/FAIL: **PASS**

Comments: _____

Deficiencies: _____

Insulated Case Circuit Breaker Test and Inspection
G2

Customer American Electric	Site Lihue International Airport	Agreement Number ET21-121
Date 3/22/2022	Technician Jared Helminen	Location Lihue, HI
Manufacturer General Electric	Model Power Break	Equipment Tag ID G2
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587, AEMC 6240)	Test Equipment Last Calibration Date 8/20/2020	SERIAL NUMBER AC16367-1
Nameplate		Substation Primary

Ambient Temperature	25	°C	Trip Unit Type	MVT+	CAT number	THC1616TTEI
Humidity	60	%	Trip Unit Catalog Number	RMS9C122953	Cubicle Code	N/A
Breaker Type	GE Power Breaker		Frame Size	1600	Sensor Taps	1600
Fuse Catalog Number	N/A			Amps		
Counter as Found	N/A		Mounting			
Counter As Left	N/A		Draw-Out			
			Thermal Memory	ON		
						ZONE INTERLOCK GF ALARM ONLY

Inspection							
Proper Mounting	Inspected	Pass	No Action Needed	Insulating Members	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed	Structural Members	Inspected	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed	Contact Fingers	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed	Arcing Contacts	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed	Arc Chutes	Inspected	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed	Auxiliary Devices	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed	Overcurrent Device Battery	Inspected	Pass	No Action Needed
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed				

Overall Visual Inspection PASSED INSPECTION

Settings as Found										
	Function	Rating Plug	Function	Pickup	Delay					
Ground Fault 3W	Long	1600	0.75	X	1600	A	=	1200	A	1
	Short	1600		X		A	=	0	A	
	Instantaneous		10	X	1600	A	=	16000	A	
	Ground Fault		0.2	X	1600	A	=	320	A	3 Out

Settings as Left										
	Function	Rating Plug	Function	Pickup	Delay					
Ground Fault 3W	Long	1600	0.75	X	1600	A	=	1200	A	1
	Short	1600		X		A	=	0	A	0
	Instantaneous		10	X	1600	A	=	16000	A	
	Ground Fault		0.2	X	1600	A	=	320	A	3 Out

Timing Tests						
Trip Curve (TCC) Number: GES-9913						
Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds
			Minimum	Maximum		
Long Time	3600	3XIr	8	16	11.42	11.42
			LTPU (amps)			
Short Time	16000	8XIn	0.01	0.07	0.05	0.05
			STPU (amps)			
Instantaneous	480	1XIn	0.38	0.5	0.39	0.39
			IPU (amps)			
Ground Fault	3200	100%	GFPU (amps)			

Contact Resistance Across Closed Poles						
Breaker Current Rating	Maximum Percent Load	Maximum Load	Measurements	Deviation	Deviation Pass or Fail	Overall Pass or Fail
3200	100%	3200	Phase A: 31 μΩ	10.71%	PASS	PASS
			Phase B: 35 μΩ	25.00%	PASS	
			Phase C: 28 μΩ	0.00%	PASS	

Insulation Resistance							
Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature	25	°C		
Minimum Test Voltage	1000	kVDC	Temperature Correction Factor	1.25			
Test Voltage Used	1000	kVDC	Minimum Insulation Resistance	100	MΩ		
Test Duration per Reading	60	Seconds					
State	Points	Measurements	Corrected for °C	Pass or Fail			
Closed	A to B	170	212.5	PASS			
Closed	B to C	125	156.25	PASS			
Closed	C to A	150	187.5	PASS			
Closed	A to G	105	131.25	PASS			
Closed	B to G	66	82.5	PASS			
Closed	C to G	100	125	PASS			
Open	A Line - Load	184	230	PASS			
Open	B Line - Load	2200	2750	PASS			
Open	C Line - Load	120	150	PASS			
Any	Control Wiring	2200	2750	PASS			

Comments: _____

Deficiencies: _____

Insulated Case Circuit Breaker Test and Inspection
ATS 1 Emergency

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/22/2022	Location Lihue, HI	Equipment Tag ID ATS 1 Emergency
Technician Jared Helminen	Model Power Break	SERIAL NUMBER V78657
Manufacturer General Electric	Test Equipment Last Calibration Date 8/20/2020	Substation Primary
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587, AEMC 6240)	Nameplate	

Ambient Temperature 25 °C	Trip Unit Type MVT	CAT number THCVF5612
Humidity 60 %	Trip Unit Catalog Number TP4VT206	Cubicle Code N/A
Breaker Type GE Power Breaker	Frame Size 1200 Amps	Sensor Taps 1200
Fuse Catalog Number N/A	Mounting Draw-Out	Thermal Memory ON
Counter as Found N/A	Thermal Memory ON	Cond Size and Type N/A
Counter As Left N/A	Thermal Memory ON	Cond Size and Type N/A

Inspection	Inspected	Pass	No Action Needed	Inspected	Pass	No Action Needed	
Proper Mounting	Inspected	Pass	No Action Needed	Insulating Members	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed	Structural Members	Inspected	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed	Contact Fingers	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed	Arcing Contacts	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed	Arc Chutes	Inspected	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed	Auxiliary Devices	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed				
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed	Overcurrent Device Battery	No battery	NA	NA

Overall Visual Inspection PASSED INSPECTION

Settings as Found	Function	Pickup	Delay
Ground Fault 3W	Rating Plug	1200 Long	1
	Sensor Tap	1200 Short	0
	Instantaneous	10	12000
	Ground Fault	0.2	240

Settings as Left	Function	Pickup	Delay
Ground Fault 3W	Rating Plug	1200 Long	1
	Sensor Tap	1200 Short	0
	Instantaneous	10	12000
	Ground Fault	0.2	240

Trip Curve (TCC) Number GES-9910	Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds
				Minimum	Maximum		
Long Time	LTPU (amps)	3600	3Xlr	77	131	80.7	80.7
		12000	8Xln	0.01	0.07	11500	11500
Short Time	STPU (amps)	360	1Xln	0.7	1.2	0.85	0.85
		360	1Xln	0.7	1.2	244	244

Contact Resistance Across Closed Poles	Breaker Current Rating	Maximum Percent Load	Maximum Load	Measurements	Deviation	Deviation Pass or Fail	Overall
							Pass or Fail
	1200	100%	1200	Phase A: 27	0.00%	PASS	PASS
				Phase B: 27	0.00%	PASS	
				Phase C: 28	3.70%	PASS	

Insulation Resistance	Breaker Voltage Rating	Minimum Test Voltage	Test Voltage Used	Test Duration per Reading	VAC Phase to Phase		Insulation Temperature	Temperature Correction Factor	Minimum Insulation Resistance	Pass or Fail
					Measurements	Corrected for °C				
	600	1000	1000	60	MΩ	MΩ	25 °C	1.25	100 MΩ	

OVERALL PASS/FAIL: PASS

Comments: _____

Deficiencies: _____

**Insulated Case Circuit Breaker Test and Inspection
Capacitor**

Customer American Electric		Site Lihue International Airport		Agreement Number ET22-121	
Date 3/21/2022		Technician Jared Helminen		Equipment Tag ID Capacitor	
Manufacturer General Electric		Model Power Break		SERIAL NUMBER V110841	
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587, AEMC 6240)		Test Equipment Last Calibration Date 8/20/2020		Substation Primary	

Nameplate	
Ambient Temperature: 25 °C	Trip Unit Type: MVT RMS-9
Humidity: 60 %	Trip Unit Catalog Number: TR16S1200
Breaker Type: GE Power Breaker	Frame Size: 1600 Amps
Fuse Catalog Number: N/A	CAT number: TP1616SS
Counter as Found: N/A	Cubicle Code: N/A
Counter As Left: N/A	Sensor Taps: 1600
Mounting: _____	Cond Size and Type: N/A
Thermal Memory: ON	ZONE INTERLOCK: OFF
	GF ALARM ONLY: ON

Inspection			
Proper Mounting	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed
Insulating Members	Inspected	Pass	No Action Needed
Structural Members	Inspected	Pass	No Action Needed
Contact Fingers	Inspected	Pass	No Action Needed
Arcing Contacts	Inspected	Pass	No Action Needed
Arc Chutes	Inspected	Pass	No Action Needed
Auxiliary Devices	Inspected	Pass	No Action Needed
Overcurrent Device Battery	No battery	NA	NA
Overall Visual Inspection PASSED INSPECTION			

Settings as Found											
Ground Fault 3W	Rating Plug	1200	Long	1	X	1200	A	=	1200	A	Delay: Max
	Sensor Tap	1600	Short	3	X	1200	A	=	3600	A	Min (Out)
			Instantaneous	3	X	1200	A	=	3600	A	
			Ground Fault	0.2	X	1200	A	=	240	A	Min (Out)
	Settings as Left										
Ground Fault 3W	Rating Plug	1200	Long	1	X	1200	A	=	1200	A	Delay: Max
	Sensor Tap	1600	Short	3	X	1200	A	=	3600	A	Min (Out)
			Instantaneous	3	X	1200	A	=	3600	A	
			Ground Fault	0.2	X	1200	A	=	240	A	Min (Out)

Timing Tests									
Trip Curve (TCC) Number: GES-9910									
Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds			
			Minimum	Maximum					
Long Time	3600	3Xlr	80	120	94.99	94.99			
Short Time	4800	6Xlr	0.08	0.17	0.12	0.12			
Instantaneous	4800	8Xlr	0.01	0.07	0.05	0.05			
Ground Fault	360	0.3Xlr	0.08	0.17	0.12	0.12			

Contact Resistance Across Closed Poles									
Breaker Current Rating	1200	Amps	Measurements			Deviation	Deviation	Overall	
Maximum Percent Load	100%		Phase A	32		0.00%	PASS	PASS	
Maximum Load	1200		Phase B	34		6.25%	PASS		
		Phase C	36		12.50%	PASS			

Insulation Resistance									
Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature: 25 °C						
Minimum Test Voltage	1000		Temperature Correction Factor: 1.25						
Test Voltage Used	1000		Minimum Insulation Resistance: 100 MΩ						
Test Duration per Reading	60								
State	Points	Measurements	Corrected for °C		Pass or Fail				
Closed	A to B	2200	2750		PASS				
Closed	B to C	2200	2750		PASS				
Closed	C to A	2200	2750		PASS				
Closed	A to G	1700	2125		PASS				
Closed	B to G	1700	2125		PASS				
Closed	C to G	2100	2625		PASS				
Open	A Line - Load	2200	2750		PASS				
Open	B Line - Load	2200	2750		PASS				
Open	C Line - Load	2200	2750		PASS				
Any	Control Wiring	2200	2750		PASS				
OVERALL PASS/FAIL: PASS									

Comments: _____
 Deficiencies: _____

**Insulated Case Circuit Breaker Test and Inspection
Main Breaker #1**

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/23/2022	Location Lihue, HI	Equipment Tag ID Main Breaker #1
Technician Jared Helminen	Model Power Break	SERIAL NUMBER 78395
Manufacturer General Electric	Test Equipment Last Calibration Date 8/20/2020	Substation Primary
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587,AEMC 6240)		

Nameplate

Ambient Temperature	25 °C	Trip Unit Type	MVT RMS-9	CAT number	THCBV9640K
Humidity	60 %	Trip Unit Catalog Number	TR40S4000	Cubicle Code	N/A
Breaker Type	GE Power Breaker	Frame Size	4000 Amps	Sensor Taps	4000
Fuse Catalog Number	N/A	Mounting		Cond Size and Type	N/A
Counter as Found	N/A	Thermal Memory	OFF		
Counter As Left	N/A	Draw-Out		ZONE INTERLOCK	OFF
				GF ALARM ONLY	ON

Inspection

Proper Mounting	Inspected	Pass	No Action Needed	Insulating Members	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed	Structural Members	Inspected	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed	Contact Fingers	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed	Arcing Contacts	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed	Arc Chutes	Inspected	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed	Auxiliary Devices	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed	Overcurrent Device Battery	No battery	NA	NA
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed				

Overall Visual Inspection PASSED INSPECTION

Settings as Found

Ground Fault 3W	Rating Plug	4000	Function	Long	0.6	X	Pickup	4000	A	=	2400	A	Delay	3
	Sensor Tap	4000	Short	4	X	2400	A	=	9600	A	Int (Out)			
			Instantaneous	2	X	4000	A	=	8000	A				
			Ground Fault	0.3	X	4000	A	=	1200	A	Int (In)			

Settings as Left

Ground Fault 3W	Rating Plug	4000	Function	Long	0.6	X	Pickup	4000	A	=	2400	A	Delay	3
	Sensor Tap	4000	Short	4	X	2400	A	=	9600	A	Int (Out)			
			Instantaneous	2	X	4000	A	=	8000	A				
			Ground Fault	0.3	X	4000	A	=	1200	A	Int (In)			

Timing Tests

Trip Curve (TCC) Number GES-9910						
Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds
			Minimum	Maximum		
Long Time	7200	3Xlr	40	60	45.62	45.62
	LTPU (amps)					
Short Time	9600	8Xln	0.22	0.32	0.25	0.25
	STPU (amps)					
Instantaneous	12000	.45Xln	0.01	0.07	0.05	0.05
	IPU (amps)					
Ground Fault	1800	GFPU (amps)	0.7	1.2	0.82	0.82

Contact Resistance Across Closed Poles

Breaker Current Rating	4000	Amps	Measurements μΩ	Deviation	Deviation Pass or Fail	Overall Pass or Fail
Maximum Percent Load	100%					
Maximum Load	4000					
		Phase A				
		Phase B	15	0.00%	PASS	
		Phase C	18	20.00%	PASS	

Insulation Resistance

Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature		25 °C
Minimum Test Voltage	1000		Temperature Correction Factor		1.25
Test Voltage Used	1000		Minimum Insulation Resistance		100 MΩ
Test Duration per Reading	60				

State	Points	Measurements		Corrected for °C	Pass or Fail
		MΩ	MΩ		
Closed	A to B	124	155		PASS
Closed	B to C	18	22.5		PASS
Closed	C to A	168	210		PASS
Closed	A to G	104	130		PASS
Closed	B to G	240	300		PASS
Closed	C to G	300	375		PASS
Open	A Line - Load	2200	2750		PASS
Open	B Line - Load	2200	2750		PASS
Open	C Line - Load	2200	2750		PASS
Any	Control Wiring	2200	2750		PASS

OVERALL PASS/FAIL: PASS

Comments: _____

Deficiencies: _____

Insulated Case Circuit Breaker Test and Inspection
Tie Breaker

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/23/2022	Technician Jared Helminen	Location Lihue, HI
Manufacturer General Electric	Model Power Break	Equipment Tag ID Tie Breaker
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587,AEMC 6240)	Test Equipment Last Calibration Date 8/20/2020	SERIAL NUMBER V76641
Nameplate		Substation Primary

Ambient Temperature	25	°C	Trip Unit Type	MVT	CAT number	TCVVF9640R
Humidity	60	%	Trip Unit Catalog Number	TP9TV40SLGA3	Cubicle Code	N/A
Breaker Type	GE Power Breaker		Frame Size	4000	Sensor Taps	4000
Fuse Catalog Number	N/A				Cond Size and Type	N/A
Counter as Found	N/A		Mounting			
Counter As Left	N/A		Draw-Out			
			Thermal Memory	OFF	ZONE INTERLOCK	OFF
					GF ALARM ONLY	ON

Inspection

Proper Mounting	Inspected	Pass	No Action Needed	Insulating Members	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed	Structural Members	Inspected	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed	Contact Fingers	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed	Arcing Contacts	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed	Arc Chutes	Inspected	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed	Auxiliary Devices	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed				
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed	Overcurrent Device Battery	No battery	NA	NA

Overall Visual Inspection PASSED INSPECTION

Settings as Found

	Function	Pickup	Delay
GroundFault 3W	Rating Plug	4000 Long	0.6
	Sensor Tap	4000 Short	4
		Instantaneous	2
		Ground Fault	0.3

Settings as Left

	Function	Pickup	Delay
GroundFault 3W	Rating Plug	4000 Long	0.6
	Sensor Tap	4000 Short	4
		Instantaneous	2
		Ground Fault	0.3

Timing Tests

Trip Curve (TCC) Number	Function		Time Band		As Found seconds	As Left seconds
	Test Amps	Current Multiple	Minimum	Maximum		
GES-9910	7200	3Xlr	40	60	40.5	40.5
			LTPU (amps)			2440
Short Time	10800		0.22	0.32	0.30	0.30
			STPU (amps)			9450
Instantaneous	12000	8XIn	0.01	0.07	0.05	0.05
			IPU (amps)			12100
Ground Fault	1800	1XIn	0.77	1.31	0.85	0.85
			GFPU (amps)			1184

Contact Resistance Across Closed Poles

Breaker Current Rating	4000	Amps	Measurements	Deviation	Deviation Pass or Fail	Overall Pass or Fail
Maximum Percent Load	100%	%	Phase A	21	16.67%	PASS
Maximum Load	4000		Phase B	18	0.00%	PASS
			Phase C	22	22.22%	PASS

Insulation Resistance

Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature	25	°C
Minimum Test Voltage	1000	kVDC	Temperature Correction Factor	1.25	
Test Voltage Used	1000	kVDC	Minimum Insulation Resistance	100	MΩ
Test Duration per Reading	60	Seconds			

State	Points	Measurements	Corrected for °C	Pass or Fail
Closed	A to B	20	25	PASS
Closed	B to C	22	27.5	PASS
Closed	C to A	27	33.75	PASS
Closed	A to G	18	22.5	PASS
Closed	B to G	17	21.25	PASS
Closed	C to G	18	22.5	PASS
Open	A Line - Load	80	100	PASS
Open	B Line - Load	60	75	PASS
Open	C Line - Load	130	162.5	PASS
Any	Control Wiring	1700	2125	PASS

OVERALL PASS/FAIL: **PASS**

Comments

Deficiencies

**Insulated Case Circuit Breaker Test and Inspection
ATS 2**

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/23/2022	Location Lihue, HI	Equipment Tag ID ATS 2
Technician Jared Helminen	Model Power Break	SERIAL NUMBER V77612
Manufacturer General Electric	Test Equipment Last Calibration Date 8/20/2020	Substation Primary
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587, AEMC 6240)		

Ambient Temperature	25 °C	Trip Unit Type	MVT	CAT number	TPVVF5612RB
Humidity	60 %	Trip Unit Catalog Number	TP9TV20SLGB	Cubicle Code	N/A
Breaker Type	GE Power Breaker	Frame Size	1200 Amps	Sensor Taps	1200
Fuse Catalog Number	N/A	Mounting		Cond Size and Type	N/A
Counter as Found	N/A	Draw-Out			
Counter As Left	N/A	Thermal Memory	ON		

ZONE INTERLOCK
GF ALARM ONLY

Inspection			
Proper Mounting	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed
Insulating Members	Inspected	Pass	No Action Needed
Structural Members	Inspected	Pass	No Action Needed
Contact Fingers	Inspected	Pass	No Action Needed
Arcing Contacts	Inspected	Pass	No Action Needed
Arc Chutes	Inspected	Pass	No Action Needed
Auxiliary Devices	Inspected	Pass	No Action Needed
Overcurrent Device Battery	No battery	NA	NA

Overall Visual Inspection PASSED INSPECTION

Settings as Found												
Ground Fault 3W	Rating Plug	1200	Function	Long	1	X	Pickup	1200 A	=	1200 A	Delay	4
	Sensor Tap	1200	Short	5	X	1200 A	=	6000 A		Max		
			Instantaneous	10	X	1200 A	=	12000 A				
			Ground Fault	0.25	X	1200 A	=	300 A		Max		

Settings as Left												
Ground Fault 3W	Rating Plug	1200	Function	Long	1	X	Pickup	1200 A	=	1200 A	Delay	4
	Sensor Tap	1200	Short	5	X	1200 A	=	6000 A		Max		
			Instantaneous	10	X	1200 A	=	12000 A				
			Ground Fault	0.25	X	1200 A	=	300 A		Max		

Timing Tests						
Trip Curve (TCC) Number GES-9910						
Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds
			Minimum	Maximum		
Long Time	3600	3XIr	80	125	108.4	108.4
	LTPU (amps)				1320	1320
Short Time	6000		0.38	0.5	0.40	0.40
	STPU (amps)				6000	6000
Instantaneous	12000	8XIn	0.01	0.07	0.05	0.05
	IPI (amps)				12000	12000
Ground Fault	450	1XIn	0.7	1.2	0.83	0.83
	GFPU (amps)				305	305

Contact Resistance Across Closed Poles						
Breaker Current Rating	1200	Amps	Phase A Phase B Phase C	Measurements	Deviation	Deviation Pass or Fail
Maximum Percent Load	100%	%		μΩ		
Maximum Load	1200			33	13.79%	PASS
				29	0.00%	PASS
				40	37.93%	PASS
				Overall Pass or Fail PASS		

Insulation Resistance						
Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature	25	°C	
Minimum Test Voltage	1000	kVDC	Temperature Correction Factor	1.25		
Test Voltage Used	1000	kVDC	Minimum Insulation Resistance	100	MΩ	
Test Duration per Reading	60	Seconds				

State	Points	Measurements	Corrected for °C	Pass or Fail
Closed	A to B	285	356.25	PASS
Closed	B to C	260	325	PASS
Closed	C to A	300	375	PASS
Closed	A to G	160	200	PASS
Closed	B to G	150	187.5	PASS
Closed	C to G	140	175	PASS
Open	A Line - Load	650	812.5	PASS
Open	B Line - Load	620	775	PASS
Open	C Line - Load	610	762.5	PASS
Any	Control Wiring	2200	2750	PASS

OVERALL PASS/FAIL: PASS

Comments: _____

Deficiencies: _____

Insulated Case Circuit Breaker Test and Inspection
ATS 4

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/24/2022	Technician Jared Helminen	Location Lihue, HI
Manufacturer General Electric	Model Power Break	Equipment Tag ID ATS 4
Test Equipment Used (Calibration Numbers) MEGGER DDA 1600 (Fluke 1587, AEMC 6240)	Test Equipment Last Calibration Date 8/20/2020	SERIAL NUMBER V76643
Nameplate		Substation Primary

Ambient Temperature	25	°C	Trip Unit Type	MVT	CAT number	TPVVF7625R
Humidity	60	%	Trip Unit Catalog Number	TP9VT30SLG	Cubicle Code	N/A
Breaker Type	GE Power Breaker		Frame Size	2500	Sensor Taps	2500
Fuse Catalog Number	N/A		Amps		Cond Size and Type	N/A
Counter as Found	N/A		Mounting			
Counter As Left	N/A		Draw-Out			
			Thermal Memory	OFF		
					ZONE INTERLOCK	OFF
					GF	ON

Inspection							
Proper Mounting	Inspected	Pass	No Action Needed	Insulating Members	Inspected	Pass	No Action Needed
Conductors Match Single Line	YES	Pass	No Action Needed	Structural Members	Inspected	Pass	No Action Needed
Feeder Designation Match Drawing	Inspected	Pass	No Action Needed	Contact Fingers	Inspected	Pass	No Action Needed
Casing Intact with no Cracking	Inspected	Pass	No Action Needed	Arcing Contacts	Inspected	Pass	No Action Needed
Bolt Torque Levels Checked	NA/DLRO	Pass	No Action Needed	Arc Chutes	Inspected	Pass	No Action Needed
Breaker Operates Correctly	Inspected	Pass	No Action Needed	Auxiliary Devices	Inspected	Pass	No Action Needed
Frame Size & Trip Unit Correct	Inspected	Pass	No Action Needed	Overcurrent Device Battery	No battery	NA	NA
Terminals Suitable for 75deg C	Inspected	Pass	No Action Needed				
Overall Visual Inspection PASSED INSPECTION							

Settings as Found										
Ground Fault 3W	Rating Plug	2500	Function	Long	1	X	Pickup	2500 A = 2500 A	Delay	3
	Sensor Tap	2500	Short	5		X	2500 A = 12500 A		Int	
			Instantaneous	10		X	2500 A = 25000 A			
			Ground Fault	0.3		X	2500 A = 750 A		Max	

Settings as Left										
Ground Fault 3W	Rating Plug	2500	Function	Long	1	X	Pickup	2500 A = 2500 A	Delay	3
	Sensor Tap	2500	Short	5		X	2500 A = 12500 A		Int	
			Instantaneous	10		X	2500 A = 25000 A			
			Ground Fault	0.3		X	2500 A = 750 A		Max	

Timing Tests						
Trip Curve (TCC) Number GES-9910						
Function	Test Amps	Current Multiple	Time Band		As Found seconds	As Left seconds
			Minimum	Maximum		
Long Time	7500	3Xlr	40	60	49.8	49.8
	LTPU (amps)				2550	2550
Short Time	18750	7.5Xlr	0.22	0.32	0.29	0.29
	STPU (amps)				12650	12650
Instantaneous	25000	8Xln	0.01	0.07	0.05	0.05
	IPU (amps)				25100	25100
Ground Fault	1800	0.45Xln	0.7	1.2	0.83	0.83
	GFPU (amps)				770	770

Contact Resistance Across Closed Poles						
Breaker Current Rating	2500	Amps	Measurements µΩ	Deviation	Deviation Pass or Fail	Overall Pass or Fail
Maximum Percent Load	100%	%				
Maximum Load	2500					
			Phase A	22	0.00%	PASS
			Phase B	22	0.00%	PASS
			Phase C	22	0.00%	PASS

Insulation Resistance					
Breaker Voltage Rating	600	VAC Phase to Phase	Insulation Temperature	25	°C
Minimum Test Voltage	1000	kVDC	Temperature Correction Factor	1.25	
Test Voltage Used	1000	kVDC	Minimum Insulation Resistance	100	MΩ
Test Duration per Reading	60	Seconds			
State	Points	Measurements MΩ	Corrected for °C MΩ	Pass or Fail	
Closed	A to B	1200	1500	PASS	
Closed	B to C	2200	2750	PASS	
Closed	C to A	2200	2750	PASS	
Closed	A to G	210	262.5	PASS	
Closed	B to G	140	175	PASS	
Closed	C to G	1200	1500	PASS	
Open	A Line - Load	2200	2750	PASS	
Open	B Line - Load	2200	2750	PASS	
Open	C Line - Load	2200	2750	PASS	
Any	Control Wiring	2200	2750	PASS	
				OVERALL PASS/FAIL: PASS	

Comments: _____

Deficiencies: _____



AUTOMATIC TRANSFER SWITCHES



**AUTOMATIC TRANSFER SWITCH TEST
ATS 1**

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/21/2022	Technician Brad Helminen	Location Lihue, HI
Manufacturer CAT	Model MX 250	Equipment Tag ID ATS 1
Test Equipment Used (Calibration Numbers) MEGGER MPRT 8430	Test Equipment Last Calibration Date Sep-21	Serial Number TSC01892

CATALOG NO.	2502265	TYPE	MX	AMPACITY	1200 Amps
WIRING NO.	CFS	SYSTEM VOLTAGE L-L	480		
AMBIENT TEMP.	25 °C	HUMIDITY:	66 %		
INSTALLED OPTIONS			MICROPROCESSOR		

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
OVERALL CLEANLINESS	YES	GOOD	C/L
INSULATING MEMBERS	YES	GOOD	C/L
MECHANICAL CONNECTIONS	YES	GOOD	C/L
STRUCTURAL MEMBERS	YES	DIRTY	C/L
MAIN CONTACTS	YES	EXCELLENT	NA

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
ARCING CHUTES	YES	DIRTY	C
OPERATING MECHANISM	YES	GOOD	C/L
CONTACT SEQUENCE	YES	GOOD	C
GROUND CONNECTION	YES	GOOD	C
AUXILIARY DEVICES	YES	GOOD	C

TIME DELAYS	SPECIFIED		AS FOUND		AS LEFT	
OVERWRITE MOMENTARY OUTAGES	3 SEC		3.178		3.178	
FACTORY SET @	3	SEC				
TRANSFER TO EMERGENCY ADJUSTMENT	1 SEC		1.631		1.631	
FACTORY SET @	1 + 5	SEC				
NO LOAD ENGINE COOL DOWN ADJUSTMENT	300 SEC		301.5 SEC		301.5 SEC	
FACTORY SET @	5	MIN				
RE-TRANSFER TO NORMAL ADJUSTMENT	1800 SEC		1801.41 SEC		1801.41 SEC	
FACTORY SET @	30	MIN				
SENSOR SETTINGS	NOMINAL VOLTAGE:		VOLTS & HZ		%	
NORMAL SOURCE PICKUP VOLTAGE	PHASE A	432	90	433.5	90.31%	433.5
ADJUSTMENT RANGE:	PHASE B	432	90	433.5	90.31%	433.5
FACTORY SET @	PHASE C	432	90	433.5	90.31%	433.5
NORMAL SOURCE DROPOUT VOLTAGE	PHASE A	384	80	384.9	80.19%	384.9
ADJUSTMENT RANGE:	PHASE B	384	80	384.9	80.19%	384.9
FACTORY SET @	PHASE C	384	80	384.9	80.19%	384.9
EMERGENCY SOURCE VOLTAGE	PICKUP	432	90	437.1	91.06%	437.1
FACTORY SET @	DROPOUT	384	80	386.3	80.48%	386.3
EMERGENCY SOURCE FREQUENCY	PICKUP	57	95	57.06	95.10%	57.06
FACTORY SET @	DROPOUT	54	90	53.78	89.63%	53.78

Comments: Contact Resistance Normal A = 69 B = 65 C = 71 Contact Resistance Emergency A = 88 B = 81 C = 86

Deficiencies: Several bulbs need to be replaced on the indicating panel of the door. This does not affect the operation of the switch.



AUTOMATIC TRANSFER SWITCH TEST

ATS 2

Customer American Electric	Technician Brad Helminen	Site Lihue International Airport	Agreement Number ET22-121
Date 3/21/2022		Location Lihue, HI	Equipment Tag ID ATS 2
Manufacturer CAT		Model MX 250	Serial Number TSC01593
Test Equipment Used (Calibration Numbers) MEGGER MPRT 8430		Test Equipment Last Calibration Date Sep-21	

CATALOG NO.	2502265	TYPE	MX	AMPACITY	1200 Amps
WIRING NO.	CFS	SYSTEM VOLTAGE L-L	480		
AMBIENT TEMP.	25 °C	HUMIDITY:	66 %		
INSTALLED OPTIONS			MICROPROCESSOR		

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
OVERALL CLEANLINESS	YES	GOOD	C/L
INSULATING MEMBERS	YES	GOOD	C/L
MECHANICAL CONNECTIONS	YES	GOOD	C/L
STRUCTURAL MEMBERS	YES	DIRTY	C/L
MAIN CONTACTS	YES	EXCELLENT	NA

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
ARCING CHUTES	YES	DIRTY	C
OPERATING MECHANISM	YES	GOOD	C/L
CONTACT SEQUENCE	YES	GOOD	C
GROUND CONNECTION	YES	GOOD	C
AUXILIARY DEVICES	YES	GOOD	C

TIME DELAYS	SPECIFIED		AS FOUND		AS LEFT	
OVERVERRIDE MOMENTARY OUTAGES	3 SEC		3 SEC		3 SEC	
FACTORY SET @ 3 SEC						
TRANSFER TO EMERGENCY ADJUSTMENT	1 SEC		1 SEC		1 SEC	
FACTORY SET @ 1 SEC						
NO LOAD ENGINE COOL DOWN ADJUSTMENT	300 SEC		300 SEC		300 SEC	
FACTORY SET @ 5 MIN						
RE-TRANSFER TO NORMAL ADJUSTMENT	600 SEC		600 SEC		600 SEC	
FACTORY SET @ 10 MIN						
SENSOR SETTINGS NOMINAL VOLTAGE:	VOLTS & HZ	%	VOLTS & HZ	%	VOLTS & HZ	%
NORMAL SOURCE PICKUP VOLTAGE	PHASE A	432	90	---	---	---
ADJUSTMENT RANGE:	PHASE B	432	90	---	---	---
FACTORY SET @ 90 %	PHASE C	432	90	---	---	---
NORMAL SOURCE DROPOUT VOLTAGE	PHASE A	384	80	---	---	---
ADJUSTMENT RANGE:	PHASE B	384	80	---	---	---
FACTORY SET @ 80 %	PHASE C	384	80	---	---	---
EMERGENCY SOURCE VOLTAGE ADJUSTMENT	PICKUP	432	90	---	---	---
FACTORY SET @ 80 %	DROPOUT	384	80	---	---	---
EMERGENCY SOURCE FREQUENCY	PICKUP	57	95	---	---	---
FACTORY SET @ 90 %	DROPOUT	54	90	---	---	---

Comments:

Deficiencies: The ATS was functional tested by simulating an outage, but could not be fully tested as the automatic portion of the bypass-isolation switch will not rack out. Several bulbs need to be replaced on the indicating panel of the door. This does not affect the operation of the switch.



AUTOMATIC TRANSFER SWITCH TEST

ATS 4

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 1/26/2021	Technician Brad Helminen	Equipment Tag ID ATS 4
Manufacturer WESTINGHOUSE	Model ATC-600	Serial Number 52359
Test Equipment Used (Calibration Numbers) MEGGER MPRT 8430	Test Equipment Last Calibration Date Sep-21	

CATALOG NO. 2D78589G50 TYPE ATVSP AMPACITY 3000 Amps
 WIRING NO. 5724B09 SYSTEM VOLTAGE L-L 480
 AMBIENT TEMP. 25 °C HUMIDITY: 66 % MICROPROCESSOR
 INSTALLED OPTIONS

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
OVERALL CLEANLINESS	YES	GOOD	C/L
INSULATING MEMBERS	YES	GOOD	C/L
MECHANICAL CONNECTIONS	YES	GOOD	C/L
STRUCTURAL MEMBERS	YES	DIRTY	C/L
MAIN CONTACTS	YES	EXCELLENT	NA

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
ARCING CHUTES	YES	DIRTY	C
OPERATING MECHANISM	YES	GOOD	C/L
CONTACT SEQUENCE	YES	GOOD	C
GROUND CONNECTION	YES	GOOD	C
AUXILIARY DEVICES	YES	GOOD	C

TIME DELAYS		SPECIFIED		AS FOUND		AS LEFT		
OVERRIDE MOMENTARY OUTAGES		3 SEC		3.21 SEC		3.21 SEC		
FACTORY SET @ 3 SEC								
TRANSFER TO EMERGENCY ADJUSTMENT		6 SEC		6.18 SEC		6.18 SEC		
FACTORY SET @ 1 + 5 SEC								
NO LOAD ENGINE COOL DOWN ADJUSTMENT		120 SEC		119.68 SEC		119.68 SEC		
FACTORY SET @ 2 MIN								
RE-TRANSFER TO NORMAL ADJUSTMENT		300 SEC		300.4 SEC		300.4 SEC		
FACTORY SET @ 5 MIN								
SENSOR SETTINGS NOMINAL VOLTAGE:		VOLTS & HZ	%	VOLTS & HZ	%	VOLTS & HZ	%	
NORMAL SOURCE PICKUP VOLTAGE		PHASE A	432	90	435.60	90.75%	435.6	90.75%
ADJUSTMENT RANGE:		PHASE B	432	90	435.60	90.75%	435.6	90.75%
FACTORY SET @ 90 %		PHASE C	432	90	435.60	90.75%	435.6	90.75%
NORMAL SOURCE DROPOUT VOLTAGE		PHASE A	384	80	389.50	81.15%	389.5	81.15%
ADJUSTMENT RANGE:		PHASE B	384	80	389.50	81.15%	389.5	81.15%
FACTORY SET @ 80 %		PHASE C	384	80	389.50	81.15%	389.5	81.15%
EMERGENCY SOURCE VOLTAGE		PICKUP	432	90	435.1	90.65%	435.1	90.65%
FACTORY SET @ 80 %		DROPOUT	384	80	387.3	80.69%	387.3	80.69%
EMERGENCY SOURCE FREQUENCY		PICKUP	57.6	95	57.58	95.97%	57.58	95.97%
FACTORY SET @ 90 %		DROPOUT	56.4	90	56.42	94.03%	56.42	94.03%

Comments:

Deficiencies:



AUTOMATIC TRANSFER SWITCH TEST
Maintenance Baseyard ATS

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/22/2022	Technician Brad Helminen	Location Lihue, HI
Manufacturer CAT	Model MX 150	Equipment Tag ID Maintenance Baseyard ATS
Test Equipment Used (Calibration Numbers) MEGGER MPRT 8430	Test Equipment Last Calibration Date Sep-21	Serial Number TSA12651

CATALOG NO. 1526846 TYPE MX AMPACITY 400 Amps
 WIRING NO. CTG SYSTEM VOLTAGE L-L 480
 AMBIENT TEMP. 24 °C HUMIDITY: 67 % MICROPROCESSOR
 INSTALLED OPTIONS _____

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
OVERALL CLEANLINESS	YES	DIRTY	C/L
INSULATING MEMBERS	YES	DIRTY	C/L
MECHANICAL CONNECTIONS	YES	GOOD	C/L
STRUCTURAL MEMBERS	YES	DIRTY	C/L
MAIN CONTACTS	YES	EXCELLENT	NA

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
ARCING CHUTES	YES	DIRTY	C
OPERATING MECHANISM	YES	GOOD	C/L
CONTACT SEQUENCE	YES	GOOD	C
GROUND CONNECTION	YES	GOOD	C
AUXILIARY DEVICES	YES	GOOD	C

TIME DELAYS	SPECIFIED		AS FOUND		AS LEFT	
OVERWRITE MOMENTARY OUTAGES	5 SEC		5.200 SEC		5.200 SEC	
FACTORY SET @ 3 SEC	1 SEC		1.263 SEC		1.263 SEC	
TRANSFER TO EMERGENCY	300 SEC		301.5 SEC		301.5 SEC	
FACTORY SET @ 1 SEC	900 SEC		900.0 SEC		900.0 SEC	
NO LOAD ENGINE COOL DOWN	VOLTS & HZ		VOLTS & HZ		VOLTS & HZ	
FACTORY SET @ 5 MIN	PHASE A	432	90	434.5	90.52%	434.5
RE-TRANSFER TO NORMAL	PHASE B	432	90	434.5	90.52%	434.5
FACTORY SET @ 15 MIN	PHASE C	432	90	434.5	90.52%	434.5
SENSOR SETTINGS NOMINAL VOLTAGE:	PHASE A	384	80	386.1	80.44%	386.1
NORMAL SOURCE PICKUP VOLTAGE	PHASE B	384	80	386.1	80.44%	386.1
ADJUSTMENT RANGE:	PHASE C	384	80	386.1	80.44%	386.1
FACTORY SET @ 90 %	PICKUP	456	95	451.7	94.10%	451.7
NORMAL SOURCE DROPOUT VOLTAGE	DROPOUT	408	85	405.5	84.48%	405.5
ADJUSTMENT RANGE:	PICKUP	57	95	56.7	94.50%	56.7
FACTORY SET @ 80 %	DROPOUT	54	90	53.9	89.83%	53.9
EMERGENCY SOURCE VOLTAGE						
FACTORY SET @ 85 %						
EMERGENCY SOURCE FREQUENCY						
FACTORY SET @ 90 %						

Comments: Contact Resistance Normal A = 240 B = 285 C = 235 Contact Resistance Emergency A = 672 B = 528 C = 498

Deficiencies:



AUTOMATIC TRANSFER SWITCH TEST

Control Tower (Airfield) ATS

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/23/2022	Technician Jesse Helminen/Brad Helminen	Location Lihue, HI
Manufacturer ASCO	Model 7000 Series	Equipment Tag ID Control Tower (Airfield) ATS
Test Equipment Used (Calibration Numbers) MEGGER MPRT 8430	Test Equipment Last Calibration Date Sep-21	Serial Number 134670

CATALOG NO. E7ADTBA3260N5XC TYPE 7000 AMPACITY 260 Amps
 WIRING NO. 617427-015 SYSTEM VOLTAGE L-L 480
 AMBIENT TEMP. 20 °C HUMIDITY: 41 % MICROPROCESSOR
 INSTALLED OPTI _____

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
OVERALL CLEANLINESS	YES	GOOD	C/L
INSULATING MEMBERS	YES	GOOD	C/L
MECHANICAL CONNECTIONS	YES	GOOD	C/L
STRUCTURAL MEMBERS	YES	DIRTY	C/L
MAIN CONTACTS	YES	EXCELLENT	NA

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
ARCING CHUTES	YES	DIRTY	C
OPERATING MECHANISM	YES	FAILED	C/L
CONTACT SEQUENCE	YES	POOR	C
GROUND CONNECTION	YES	GOOD	C
AUXILIARY DEVICES	YES	FAILED	C

TIME DELAYS		SPECIFIED		AS FOUND		AS LEFT	
OVERRIDE MOMENTARY OUTAGES		2 SEC		2.104 SEC		2.104 SEC	
FACTORY SET @ 2 SEC							
TRANSFER TO EMERGENCY ADJUSTMENT		0 SEC		0.028 SEC		0.028 SEC	
FACTORY SET @ 0 SEC							
NO LOAD ENGINE COOL DOWN		60 SEC		58.70 SEC		58.70 SEC	
FACTORY SET @ 1 MIN							
RE-TRANSFER TO NORMAL ADJUSTMENT		1800 SEC		1799 SEC		1799 SEC	
FACTORY SET @ 30 MIN							
SENSOR SETTINGS NOMINAL VOLTAGE:		VOLTS & HZ		VOLTS & HZ		VOLTS & HZ	
NORMAL SOURCE PICKUP VOLTAGE		PHASE A	432	90	434.8	90.58%	434.8
ADJUSTMENT RANGE:		PHASE B	432	90	434.8	90.58%	434.8
FACTORY SET @ 90 %		PHASE C	432	90	434.8	90.58%	434.8
NORMAL SOURCE DROPOUT VOLTAGE		PHASE A	408	85	409.1	85.23%	409.1
ADJUSTMENT RANGE:		PHASE B	408	85	409.1	85.23%	409.1
FACTORY SET @ 80 %		PHASE C	408	85	409.1	85.23%	409.1
EMERGENCY SOURCE VOLTAGE		PICKUP	432	90	434.8	90.58%	434.8
FACTORY SET @ 85 %		DROPOUT	360	75	360.4	75.08%	360.4
EMERGENCY SOURCE FREQUENCY		PICKUP	57	95	57.000	95.00%	57
FACTORY SET @ 90 %		DROPOUT	54	90	54.000	90.00%	54

Comments: The controller was able to be tested, but the mechanical switch has failed on this unit.

Deficiencies: During bypass operation to test this switch, the operating mechanism failed. The bypass mechanism of the switch cannot be inserted back into the main contacts without repairs or replacement. The manufacture date on this switch is 02/2001 and due to the age and corrosion in the unit we recommend replacement with a modern switch. One of the (2) transfer coils has failed on this unit also.



**AUTOMATIC TRANSFER SWITCH TEST
ARFF ATS**

Customer American Electric	Site Lihue International Airport	Agreement Number ET22-121
Date 3/22/2022	Location Lihue, HI	Equipment Tag ID ARFF ATS
Technician Brad Helminen	Model Group 7 Series 940 962	Serial Number 693253004
Manufacturer ASCO	Test Equipment Last Calibration Date Sep-21	
Test Equipment Used (Calibration Numbers) MEGGER MPRT 8430		

CATALOG NO. E7623600471C TYPE ASCO AMPACITY 600 Amps
 WIRING NO. 459666-002H SYSTEM VOLTAGE L-L 208
 AMBIENT TEMP. 20 °C HUMIDITY: 80 % MICROPROCESSOR
 INSTALLED OPT _____

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
OVERALL CLEANLINESS	YES	DIRTY/CORRODED	C/L
INSULATING MEMBERS	YES	DIRTY/CORRODED	C/L
MECHANICAL CONNECTIONS	YES	DIRTY/CORRODED	C/L
STRUCTURAL MEMBERS	YES	DIRTY	C/L
MAIN CONTACTS	YES	GOOD	NA

DESCRIPTION	INSPECTED	CONDITION	CLEAN/LUBE
ARCING CHUTES	YES	DIRTY	C
OPERATING MECHANISM	YES	DIRTY/CORRODED	C/L
CONTACT SEQUENCE	YES	DIRTY/CORRODED	C
GROUND CONNECTION	YES	GOOD	C
AUXILIARY DEVICES	YES	DEFECTIVE NON WORKING	C

TIME DELAYS	SPECIFIED	AS FOUND	AS LEFT
OVERWRITE MOMENTARY OUTAGES	3 SEC	NA	NA
FACTORY SET @ 3 SEC			
TRANSFER TO EMERGENCY	0 SEC	NA	NA
FACTORY SET @ 0 SEC			
NO LOAD ENGINE COOL DOWN	300 SEC	NA	NA
FACTORY SET @ 5 MIN			
RE-TRANSFER TO NORMAL	300 SEC	NA	NA
FACTORY SET @ 5 MIN			
SENSOR SETTINGS NOMINAL VOLTAGE:	VOLTS & HZ	%	VOLTS & HZ
NORMAL SOURCE PICKUP VOLTAGE	187.2	90	0 0.00%
ADJUSTMENT RANGE:	187.2	90	0 0.00%
FACTORY SET @ 90 %	187.2	90	0 0.00%
NORMAL SOURCE DROPOUT VOLTAGE	166.4	80	0 0.00%
ADJUSTMENT RANGE:	166.4	80	0 0.00%
FACTORY SET @ 80 %	166.4	80	0 0.00%
EMERGENCY SOURCE VOLTAGE	187.2	90	0 0.00%
FACTORY SET @ 80 %	166.4	80	0 0.00%
EMERGENCY SOURCE FREQUENCY	57	95	0 0.00%
FACTORY SET @ 90 %	51	85	0 0.00%

Comments: _____

Deficiencies: **THIS SWITCH DOES NOT OPERATE MECHANICALLY OR ELECTRICALLY AND WILL NEED TO BE REPLACED. THE BYPASS MECHANISM IS INOPERABLE SO TESTING CANNOT BE COMPLETED.**











AIR-EM 22.0325 BK1321-53 Addendum No. 1 (Rev. 1)
















Final Audit Report
















2022-10-05

Created:	2022-10-04
By:	Tiffany Kapoi (tiffany.i.kapoi@hawaii.gov)
Status:	Signed
Transaction ID:	CBJCHBCAABAACVMzSsTI1kkgaoBeymKYTm0Z3Zzli95B

"AIR-EM 22.0325 BK1321-53 Addendum No. 1 (Rev. 1)" History

-  Document created by Tiffany Kapoi (tiffany.i.kapoi@hawaii.gov)
2022-10-04 - 0:33:45 AM GMT
-  Document emailed to Benton Ho (benton.ho@hawaii.gov) for approval
2022-10-04 - 0:40:13 AM GMT
-  Email viewed by Benton Ho (benton.ho@hawaii.gov)
2022-10-04 - 7:50:57 PM GMT
-  Document approved by Benton Ho (benton.ho@hawaii.gov)
Approval Date: 2022-10-04 - 7:51:06 PM GMT - Time Source: server
-  Document emailed to AIR-E eSign (DOTA) (dot.air.esign.air-e@hawaii.gov) for approval
2022-10-04 - 7:51:11 PM GMT
-  Email viewed by AIR-E eSign (DOTA) (dot.air.esign.air-e@hawaii.gov)
2022-10-04 - 9:08:38 PM GMT
-  Document approval delegated to Brenda Strimpfel (brenda.strimpfel@hawaii.gov) by AIR-E eSign (DOTA) (dot.air.esign.air-e@hawaii.gov)
2022-10-04 - 9:08:46 PM GMT
-  Document emailed to Brenda Strimpfel (brenda.strimpfel@hawaii.gov) for approval
2022-10-04 - 9:08:46 PM GMT
-  Email viewed by Brenda Strimpfel (brenda.strimpfel@hawaii.gov)
2022-10-04 - 9:28:22 PM GMT
-  Document approval delegated to Sandra Kam (sandra.j.kam@hawaii.gov) by Brenda Strimpfel (brenda.strimpfel@hawaii.gov)
2022-10-04 - 9:29:36 PM GMT

-  Document emailed to Sandra Kam (sandra.j.kam@hawaii.gov) for approval
2022-10-04 - 9:29:36 PM GMT
-  Email viewed by Sandra Kam (sandra.j.kam@hawaii.gov)
2022-10-04 - 11:49:35 PM GMT
-  Document approved by Sandra Kam (sandra.j.kam@hawaii.gov)
Approval Date: 2022-10-04 - 11:52:40 PM GMT - Time Source: server
-  Document emailed to dot.admin.dep-s_esign@hawaii.gov for approval
2022-10-04 - 11:52:41 PM GMT
-  Email viewed by dot.admin.dep-s_esign@hawaii.gov
2022-10-05 - 0:09:52 AM GMT
-  Document approval delegated to Deborah Kuwaye (deborah.k.kuwaye@hawaii.gov) by dot.admin.dep-s_esign@hawaii.gov
2022-10-05 - 0:10:02 AM GMT
-  Document approval delegated to dot.admin.dir_esign@hawaii.gov by Deborah Kuwaye (deborah.k.kuwaye@hawaii.gov)
2022-10-05 - 0:11:03 AM GMT
-  Document emailed to Deborah Kuwaye (deborah.k.kuwaye@hawaii.gov) for approval
2022-10-05 - 0:11:04 AM GMT
-  Document emailed to dot.admin.dir_esign@hawaii.gov for approval
2022-10-05 - 0:11:04 AM GMT
-  Email viewed by dot.admin.dir_esign@hawaii.gov
2022-10-05 - 1:05:44 AM GMT
-  Document approval delegated to Leslie Ah Sam (leslie.ahsam@hawaii.gov) by dot.admin.dir_esign@hawaii.gov
2022-10-05 - 1:05:47 AM GMT
-  Document approval delegated to Grace Ichikawa (grace.ichikawa@hawaii.gov) by Leslie Ah Sam (leslie.ahsam@hawaii.gov)
2022-10-05 - 1:05:59 AM GMT
-  Document emailed to Leslie Ah Sam (leslie.ahsam@hawaii.gov) for approval
2022-10-05 - 1:05:59 AM GMT
-  Document emailed to Grace Ichikawa (grace.ichikawa@hawaii.gov) for approval
2022-10-05 - 1:05:59 AM GMT
-  Email viewed by Grace Ichikawa (grace.ichikawa@hawaii.gov)
2022-10-05 - 1:08:05 AM GMT

-  Document approval delegated to Jade Butay (jade.butay@hawaii.gov) by Grace Ichikawa (grace.ichikawa@hawaii.gov)
2022-10-05 - 1:08:19 AM GMT
-  Document emailed to Jade Butay (jade.butay@hawaii.gov) for approval
2022-10-05 - 1:08:20 AM GMT
-  Email viewed by Jade Butay (jade.butay@hawaii.gov)
2022-10-05 - 1:08:34 AM GMT
-  Document approved by Jade Butay (jade.butay@hawaii.gov)
Approval Date: 2022-10-05 - 1:08:44 AM GMT - Time Source: server
-  Document emailed to dot.admin.dir_esign@hawaii.gov for signature
2022-10-05 - 1:08:45 AM GMT
-  Email viewed by dot.admin.dir_esign@hawaii.gov
2022-10-05 - 2:00:54 AM GMT
-  Document signing delegated to Leslie Ah Sam (leslie.ahsam@hawaii.gov) by dot.admin.dir_esign@hawaii.gov
2022-10-05 - 2:00:57 AM GMT
-  Document signing delegated to Grace Ichikawa (grace.ichikawa@hawaii.gov) by Leslie Ah Sam (leslie.ahsam@hawaii.gov)
2022-10-05 - 2:01:04 AM GMT
-  Document emailed to Grace Ichikawa (grace.ichikawa@hawaii.gov) for signature
2022-10-05 - 2:01:05 AM GMT
-  Document emailed to Leslie Ah Sam (leslie.ahsam@hawaii.gov) for signature
2022-10-05 - 2:01:05 AM GMT
-  Email viewed by Grace Ichikawa (grace.ichikawa@hawaii.gov)
2022-10-05 - 2:35:15 AM GMT
-  Document signing delegated to Jade Butay (jade.butay@hawaii.gov) by Grace Ichikawa (grace.ichikawa@hawaii.gov)
2022-10-05 - 2:35:22 AM GMT
-  Document emailed to Jade Butay (jade.butay@hawaii.gov) for signature
2022-10-05 - 2:35:22 AM GMT
-  Email viewed by Jade Butay (jade.butay@hawaii.gov)
2022-10-05 - 3:07:01 AM GMT
-  Document e-signed by Jade Butay (jade.butay@hawaii.gov)
Signature Date: 2022-10-05 - 3:07:23 AM GMT - Time Source: server

✔ Agreement completed.

2022-10-05 - 3:07:23 AM GMT