

STATE OF HAWAII  
 DEPARTMENT OF LAND AND NATURAL RESOURCES  
 ENGINEERING DIVISION  
 FOR  
 LAND DIVISION

JOB NO. E00BO99A

# DLNR LAND OFFICE IMPROVEMENTS KALANIMOKU BUILDING, ROOM 220

HONOLULU, OAHU, HAWAII

TMK: (1) 2-1-033: 025




## INDEX

DESCRIPTION	DRAWING NO.	SHEET NO.
TITLE, PROJECT LOCATION, VICINITY MAP, DRAWING INDEX	T-1	1
GENERAL NOTES, CONFORMANCE STATEMENT, PROJECT DATA, ABBREVIATIONS, SITE PLAN, ARCHITECTURAL SYMBOLS / LEGEND, PROJECT DIRECTORY	T-2	2
DEMOLITION FLOOR PLAN	A-1	3
DEMOLITION CEILING PLAN	A-2	4
FINISH FLOOR PLAN	A-3	5
CEILING PLAN	A-4	6
EXISTING AND REINSTALLATION FURNITURE PLAN	A-5	7
INTERIOR ELEVATIONS	A-6	8
INTERIOR ELEVATIONS	A-7	9
INTERIOR ELEVATIONS	A-8	10
INTERIOR ELEVATION, FINISH MATERIAL SCHEDULE, FURNITURE LIST	A-9	11
DETAILS	A-10	12
PHOTOS	A-11	13

### SCOPE OF WORK DESCRIPTION

THE WORK SHALL GENERALLY CONSIST OF REPLACEMENT OF FLOORING AND WALL BASE, IN THE LAND DIVISION OFFICE ON THE SECOND FLOOR LEVEL OF THE KALANIMOKU BUILDING, RM 220. IN ADDITION, ABATEMENT OF HAZARDOUS MATERIALS, TESTING AND MONITORING WILL BE REQUIRED DURING REMOVAL WORK. REPAINTING OF EXISTING WALLS, NEW MANUAL WINDOW SHADES, TEMPORARY RELOCATION OF OFFICE FURNITURE PRIOR TO FLOORING WORK AND REINSTALLATION OF OFFICE FURNITURE.



APPROVED: \_\_\_\_\_ DATE: 04/25/2024

*Russell Tsuji*

RUSSELL Y. TSUJI  
 ADMINISTRATOR  
 LAND DIVISION  
 DEPARTMENT OF LAND AND NATURAL RESOURCES

APPROVED: \_\_\_\_\_ DATE: 04/25/2024

*Carty S. Chang*

CARTY S. CHANG, P.E.  
 CHIEF ENGINEER  
 ENGINEERING DIVISION  
 DEPARTMENT OF LAND AND NATURAL RESOURCES

ABBREVIATIONS

Table of abbreviations with columns for symbols and their corresponding full names. Includes categories like AND, CENTERLINE, EXHAUST, MATERIAL, SCHEDULE, etc.


GENERAL NOTES

- 1. VERTICAL MEASUREMENTS ARE TAKEN TO FLOOR FINISH. CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ITEMS RELATIVE TO THE SPECIFIED OR INTENDED FINISH SURFACES.
2. THE CONTRACTOR SHALL OBSERVE AND COMPLY WITH ALL FEDERAL, STATE AND LOCAL LAWS REQUIRED FOR THE PROTECTION OF PUBLIC HEALTH AND SAFETY AND ENVIRONMENTAL QUALITY.
13. WORK IN BUILDING SHALL ONLY BE ALLOWED WITHIN THE HOURS BETWEEN 7:45 AM TO 4:45 PM ON WORKING DAYS.

ADA STATEMENT

CONFORMANCE WITH THE DESIGN AND CONSTRUCTION REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT ACCESSIBILITY GUIDELINES ADMINISTERED BY THE DEPARTMENT OF JUSTICE OR THE FAIR HOUSING ACT ACCESSIBILITY GUIDELINES ADMINISTERED BY THE DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT SHALL BE EQUIVALENT TO MEETING THE ACCESSIBILITY OF THIS CODE.

SITE PLAN




PROJECT DATA

APPLICABLE CODES: INTERNATIONAL BUILDING CODE (IBC), 2018 EDITION W/ LOCAL AMENDMENTS
ZONING INFORMATION: TMK: (1) 2-1-033 : 025
STREET ADDRESS: 1151 PUNCHBOWL STREET


PROJECT DIRECTORY

OWNER: DEPARTMENT OF LAND AND NATURAL RESOURCES
ENGINEERING DIVISION: LAND DIVISION OFFICE ROOM 220
1151 PUNCHBOWL STREET HONOLULU, HAWAII 96813

ARCHITECTURAL SYMBOLS / LEGEND




Professional seal of Reid T. Mizie, Licensed Professional Architect No. 13108, Hawaii, U.S.A. Includes project title 'DLNR LAND OFFICE IMPROVEMENTS KALANIMOKU BUILDING, ROOM 220' and drawing number 'T-2'.



**1 DEMOLITION PLAN - ROOM 220**

SCALE: 3/16" = 1'-0"  
 0 2 4 6 8 12 16 FT  
 SCALE: 3/16"=1'-0"



- DEMOLITION KEY NOTES**
- EXISTING FURNITURE TO REMOVE/SALVAGE IN TWO PHASES. EXISTING FURNITURE TO BE STORED ON ONE SIDE OF ROOM WHILE WORKING ON THE OTHER SIDE. VERIFY ACTUAL FURNISHING COUNT AT TIME OF BIDDING. FURNITURE LIST AND PHOTO DOCUMENTATION TO BE SUBMITTED TO ENGINEER PRIOR TO CONSTRUCTION AND RELOCATION/ STORAGE.
  - EXISTING MODULAR WORKSTATIONS TO REMOVE/SALVAGE IN TWO PHASES. EXISTING FURNITURE TO BE STORED ON ONE SIDE OF ROOM WHILE WORKING ON THE OTHER SIDE, OR STORED ON LEVEL 04 ROOM 431 IF NEEDED. VERIFY ACTUAL FURNISHING COUNT AT TIME OF BIDDING. FURNITURE LIST AND PHOTO DOCUMENTATION TO BE SUBMITTED TO ENGINEER PRIOR TO CONSTRUCTION AND RELOCATION/ STORAGE. TOOLS ARE NEEDED TO DISASSEMBLE AND ASSEMBLE EXISTING MODULAR WORKSTATIONS PRIOR TO THE REMOVAL AND REINSTALLATION OF EXISTING MODULAR WORKSTATIONS.
  - REMOVE EXISTING CARPET, ANY ASSOCIATED ADHESIVE, AND ANY OTHER EXISTING FLOORING/ SUBFLOORING TO EXISTING CONCRETE SUBSTRATE.
  - EXISTING CONCRETE COLUMNS TO REMAIN. REMOVE RUBBER WALL BASE AT COLUMN PERIMETER.
  - REMOVE EXISTING PLASTIC FRAMING COVER IN ENTIRETY TO EXISTING CONCRETE SUBSTRATE.
- NOTES**
- OWNER TO REMOVE ALL EXISTING EQUIPMENT INCLUDING, BUT NOT LIMITED TO COMPUTERS, MONITORS, TELEPHONES, AND ALL SIMILAR EQUIPMENT AND SUPPLIES.
  - ALL WORK SHALL BE COMPLETED IN 35 CONSECUTIVE CALENDAR DAYS ON-SITE CONSTRUCTION PERIOD.
  - REFER ALSO TO SHT A-9 EXISTING FURNITURE LIST.

**LEGEND**

- REMOVE EXISTING CARPET, ADHESIVE, TO EXISTING CONCRETE SUBSTRATE, AND ALL EXISTING RUBBER COVE BASE ABATEMENT OF (E) FLOORING BELOW CARPET IS REQUIRED. DO NOT DAMAGE (E) WALL SURFACE.
- EXISTING FURNITURE SEE DEMO KEY NOTES.

**KEY PLAN**

AREA OF WORK

REVISION NO.	SYM.	DESCRIPTION	SHT. OF	DATE	APPROVED

STATE OF HAWAII  
 DEPARTMENT OF LAND AND NATURAL RESOURCES  
 LAND DIVISION

**DLNR LAND OFFICE IMPROVEMENTS  
 KALANIMOKU BUILDING, ROOM 220**


**DEMOLITION FLOOR PLAN**

DESIGNED: RTM      SUBMITTED: [Signature]  
 DRAWN: KH      DATE: 04/12/24  
 CHECKED: RTM      SCALE: AS NOTED  
 APPROVED: Carty Chang  
 E-signed 2024-04-25 05:45PM HST  
 carty.s.chang@hawaii.gov  
 State of Hawaii  
 CHIEF ENGINEER  
 OMIZU Architecture Inc. Chief Engineer


DRAWING NO.  
**A-1**




**1 DEMOLITION CEILING PLAN - ROOM 220**  
 SCALE: 3/16" = 1'-0"  
 0 2 4 6 8 12 16FT  
 SCALE: 3/16"=1'-0"



LEGEND	
	(E) LIGHT FIXTURES. (NO WORK)
	(E) CUSTOM ACOUSTIC CEILING PANELS. (NO WORK)
<b>DEMOLITION KEY NOTES:</b>	
① REMOVE EXISTING INTERIOR CEILING MOUNTED WINDOW CURTAINS / DRAPES AND ASSOCIATED TRACK AND PULLS.	
② REMOVE EXISTING INTERIOR FRAME MOUNTED WINDOW SHADES, IN ENTIRETY.	
③ REMOVE EXISTING SURFACE MOUNTED MAP ROLL.	
<b>NOTES</b>	
1. OWNER TO REMOVE ALL EXISTING EQUIPMENT INCLUDING, BUT NOT LIMITED TO COMPUTERS, MONITORS, TELEPHONES, AND ALL SIMILAR EQUIPMENT AND SUPPLIES.	
2. ALL WORK SHALL BE COMPLETED IN 35 CONSECUTIVE CALENDAR DAYS ON-SITE CONSTRUCTION PERIOD.	




**KEY PLAN**  
AREA OF WORK




REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED
STATE OF HAWAII DEPARTMENT OF LAND AND NATURAL RESOURCES LAND DIVISION					
DLNR LAND OFFICE IMPROVEMENTS KALANIMOKU BUILDING, ROOM 220					
DEMOLITION CEILING PLAN					
DESIGNED: RTM			SUBMITTED: [Signature]		
DRAWN: KH			DATE: 04/12/24		
CHECKED: RTM			SCALE: AS NOTED		
APPROVED: [Signature] Carty Chang E-signed 2024-04-25 05:45PM HST carty.s.chang@hawaii.gov State of Hawaii			DRAWING NO. <b>A-2</b>		
CHIEF ENGINEER OMIZU Architecture Inc.					

This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.




**1 FINISH FLOOR PLAN - ROOM 220**  
 SCALE: 3/16" = 1'-0"  
 0 2 4 6 8 12 16FT  
 SCALE: 3/16"=1'-0"



LEGEND	
[VCT-1]	VINYL COMPOSITE TILE W/ COVE WALL BASE
	(E) FLOOR SAFE. (NO WORK)
	(E) FLOOR ELECTRICAL RECEPTACLE. (NO WORK)
	(E) CONDUIT DROP. (NO WORK)
	8 PHOTOS (TYP) [A-11]

**NOTES**

- ALL WORK SHALL BE COMPLETED IN 35 CONSECUTIVE CALENDAR DAYS ON-SITE CONSTRUCTION PERIOD.
- REFER ALSO TO SHT A-9 EXISTING FURNITURE LIST.



REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED

STATE OF HAWAII  
DEPARTMENT OF LAND AND NATURAL RESOURCES  
LAND DIVISION

**DLNR LAND OFFICE IMPROVEMENTS  
KALANIMOKU BUILDING, ROOM 220**

**FINISH FLOOR PLAN**

DESIGNED: RTM  
DRAWN: KH  
CHECKED: RTM  
APPROVED: *Carty Chang*  
CHIEF ENGINEER


OMIZU Architecture Inc.

REID T. MIZIE  
LICENSED PROFESSIONAL ARCHITECT  
No. 13108  
HAWAII, U.S.A.


Submitted: *[Signature]*  
DATE: 04/12/24  
SCALE: AS NOTED

DRAWING NO. **A-3**

This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.




**1 CEILING PLAN - ROOM 220**  
 SCALE: 3/16" = 1'-0"  
 0 2 4 6 8 12 16FT  
 SCALE: 3/16"=1'-0"



LEGEND	
	(E) LIGHT FIXTURES. (NO WORK)
	MANUAL WINDOW ROLLER SHADES
	(E) CUSTOM ACOUSTIC CEILING PANELS. (NO WORK)

**NOTES**  
 1. ALL WORK SHALL BE COMPLETED IN 35 CONSECUTIVE CALENDAR DAYS ON-SITE CONSTRUCTION PERIOD.



**KEY PLAN**  
 AREA OF WORK

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED

REID T. MIZIE  
 LICENSED PROFESSIONAL ARCHITECT  
 No. 13108  
 HAWAII, U.S.A.

STATE OF HAWAII  
 DEPARTMENT OF LAND AND NATURAL RESOURCES  
 LAND DIVISION

**DLNR LAND OFFICE IMPROVEMENTS  
 KALANIMOKU BUILDING, ROOM 220**


**CEILING PLAN**

DESIGNED: RTM  
 DRAWN: KH  
 CHECKED: RTM  
 APPROVED: *Carty Chang*  
 CHIEF ENGINEER

SUBMITTED: *[Signature]*  
 DATE: 04/12/24  
 SCALE: AS NOTED

This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.  
 OMIZU Architecture Inc.

DRAWING NO. **A-4**





1 EXISTING AND REINSTALLATION FURNITURE PLAN - SECOND FLOOR - RM 220

SCALE: 3/16" = 1'-0"

0 2 4 6 8 12 16 FT

SCALE: 3/16"=1'-0"



- LEGEND**
- (E) FLOOR RECEPTACLE. (NO WORK)
  - (E) FLOOR SAFE. (NO WORK)
  - ▣ (E) CONDUIT DROP. (NO WORK)
- NOTES**
1. OWNER TO REMOVE ALL EXISTING EQUIPMENT INCLUDING, BUT NOT LIMITED TO COMPUTERS, MONITORS, TELEPHONES, AND ALL SIMILAR EQUIPMENT AND SUPPLIES.
  2. ALL WORK SHALL BE COMPLETED IN 35 CONSECUTIVE CALENDAR DAYS ON-SITE CONSTRUCTION PERIOD.
  3. CONTRACTOR TO CAREFULLY REMOVE, STORE, AND REINSTALL GLASS/ PLASTIC SCREENS ON PARTITIONS AT NO ADDITIONAL COST TO THE STATE.

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED

REID T. MIZIE  
LICENSED PROFESSIONAL ARCHITECT  
No. 13108  
HAWAII, U.S.A.

STATE OF HAWAII  
DEPARTMENT OF LAND AND NATURAL RESOURCES  
LAND DIVISION


DLNR LAND OFFICE IMPROVEMENTS  
KALANIMOKU BUILDING, ROOM 220

EXISTING AND REINSTALLATION  
FURNITURE PLAN

DESIGNED: RTM	SUBMITTED: [Signature]
DRAWN: KH	DATE: 04/12/24
CHECKED: RTM	SCALE: AS NOTED
APPROVED: Carty Chang E-signed 2024-04-25 05:45PM HST carty.s.chang@hawaii.gov State of Hawaii	DRAWING NO. A-5
CHIEF ENGINEER: [Signature]	OMIZU Architecture Inc.

This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.

OMIZU Architecture Inc.










**1 INTERIOR ELEVATION - EXISTING WORKSTATION AREA**  
SCALE: 1/4" = 1'-0"

SCALE: 1/4" = 1'-0"

**NOTES**  
1. REFER TO FURNITURE PLAN FOR ALL FURNITURE INCLUDING, BUT NOT LIMITED TO, WORK STATIONS, CHAIRS, FILE CABINETS AND DESKS.

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED
STATE OF HAWAII DEPARTMENT OF LAND AND NATURAL RESOURCES LAND DIVISION					
DLNR LAND OFFICE IMPROVEMENTS KALANIMOKU BUILDING, ROOM 220					
INTERIOR ELEVATIONS					
DESIGNED:	RTM	SUBMITTED:	[Signature]		
DRAWN:	KH	DATE:	04/12/24		
CHECKED:	RTM	SCALE:	AS NOTED		
APPROVED:	Carty Chang E-signed 2024-04-25 05:45PM HST carty.s.chang@hawaii.gov State of Hawaii	DRAWING NO.	A-6		
CHIEF ENGINEER	OMIZU Architecture Inc.	CHIEF ENGINEER	[Signature]		





**1 INTERIOR ELEVATION - EXISTING WORKSTATION AREA CONT.**  
 SCALE: 1/4" = 1'-0"  
 0 1 2 4 8 12 FT  
 SCALE: 1/4" = 1'-0"

**NOTES**  
 1. REFER TO FURNITURE PLAN FOR ALL FURNITURE INCLUDING, BUT NOT LIMITED TO, WORK STATIONS, CHAIRS, FILE CABINETS AND DESKS.

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED

REID T. MIZIE  
 LICENSED PROFESSIONAL ARCHITECT  
 No. 13108  
 HAWAII, U.S.A.

STATE OF HAWAII  
 DEPARTMENT OF LAND AND NATURAL RESOURCES  
 LAND DIVISION

**DLNR LAND OFFICE IMPROVEMENTS  
 KALANIMOKU BUILDING, ROOM 220**

**INTERIOR ELEVATIONS**

DESIGNED: RTM  
 DRAWN: KH  
 CHECKED: RTM  
 APPROVED: Carty Chang  
 E-signed 2024-04-25 05:45PM HST  
 carty.s.chang@hawaii.gov  
 State of Hawaii  
 Chief Engineer


This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.

OMIZU Architecture Inc.

DESIGNED: RTM  
 DRAWN: KH  
 CHECKED: RTM  
 APPROVED: Carty Chang  
 E-signed 2024-04-25 05:45PM HST  
 carty.s.chang@hawaii.gov  
 State of Hawaii  
 Chief Engineer


SUBMITTED: [Signature]  
 DATE: 04/12/24  
 SCALE: AS NOTED

DRAWING NO.  
**A-7**




**2 INTERIOR ELEVATION - EXISTING CONFERENCE ROOM**  
 SCALE: 1/4" = 1'-0"  
 0 1 2 4 8 12FT  
 SCALE: 1/4"=1'-0"

**NOTES**  
 1. REFER TO FURNITURE PLAN FOR ALL FURNITURE INCLUDING, BUT NOT LIMITED TO, WORK STATIONS, CHAIRS, FILE CABINETS AND DESKS.



**3 INTERIOR ELEVATION - EXISTING COPY ROOM**  
 SCALE: 1/4" = 1'-0"  
 0 1 2 4 8 12FT  
 SCALE: 1/4"=1'-0"

**NOTES**  
 1. REFER TO FURNITURE PLAN FOR ALL FURNITURE INCLUDING, BUT NOT LIMITED TO, WORK STATIONS, CHAIRS, FILE CABINETS AND DESKS.




**4 INTERIOR ELEVATION - EXISTING OFFICE**  
 SCALE: 1/4" = 1'-0"  
 0 1 2 4 8 12FT  
 SCALE: 1/4"=1'-0"

**NOTES**  
 1. REFER TO FURNITURE PLAN FOR ALL FURNITURE INCLUDING, BUT NOT LIMITED TO, WORK STATIONS, CHAIRS, FILE CABINETS AND DESKS.

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED
STATE OF HAWAII DEPARTMENT OF LAND AND NATURAL RESOURCES LAND DIVISION					
DLNR LAND OFFICE IMPROVEMENTS KALANIMOKU BUILDING, ROOM 220					
INTERIOR ELEVATIONS					
DESIGNED:	RTM	SUBMITTED:	[Signature]		
DRAWN:	KH	DATE:	04/12/24		
CHECKED:	RTM	SCALE:	AS NOTED		
APPROVED:	Carty Chang E-signed 2024-04-25 05:45PM HST carty.s.chang@hawaii.gov State of Hawaii	DRAWING NO.		A-8	
CHIEF ENGINEER		[Signature]		[Signature]	

This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.  
 OMIZU Architecture Inc.



**EXISTING FURNITURE LIST: TO BE SALVAGED FOR RELOCATION, TEMPORARY, STORAGE, AND FOR CONTRACTOR REINSTALLATION**

TYPE	QTY	DESCRIPTION	SIZE	TYPE	QTY	DESCRIPTION	SIZE	TYPE	QTY	DESCRIPTION	SIZE	TYPE	QTY	DESCRIPTION	SIZE	TYPE	QTY	DESCRIPTION	SIZE
CPY-1	1	COPY MACHINE	28" X 54" X 39" HT 10" TRAY	BC-2	2	BLACK LARGE BOOKCASE	13" X 35" X 71" HT	DF-1	1	7-DRAWER FILE	23.5" X 28.5" X 37" HT	WP-1	1	WOOD PODIUM	17" X 24" X 53" HT	TC-1	40	TASK CHAIRS	-
CPY-2	1	COPY MACHINE	30" X 66" X 40" HT 8" TRAY	D-1	5	DESK	30" X 60" X 28" HT	GF-1	17	GREEN FILE CABINET	18.5" X 28 X 32" HT	CL-1	1	WALL CLOCK	12"	TC-2	15	TASK CHAIRS	-
CPY-3	1	COPY MACHINE	24" X 40" X 46" HT	D-2	1	DESK	29.5" X 60" X 29" HT	MC-1	1	MEDIUM METAL CABINET	18.5" X 36" X 42" HT	TB-1	3	TACK BOARD	48" X 96"	WS-1	11	WORKSTATION	10'-10" X 9'-6" / 9'-4", TYP
CPY-4	1	COPY MACHINE	24" X 27" X 45" HT 8" TRAY	D-3	3	DESK	24" X 48" X 49" HT	MC-2	1	LARGE METAL CABINET	24" X 38" X 78" HT	WB-1	3	WHITE BOARD	24" X 36"	WS-2	10	WORKSTATION	10'-8" X 7'-10" / 7'-8"
MS-1	1	MEDIUM METAL SHELF	18.5" X 37.5" X 48" HT	D-4	2	DESK	28" X 60" X 28.5" HT	MF-1	2	2 TIER FILE	19" X 30" X 28" HT	WB-2	1	WHITE BOARD	36" X 48"	WS-3	4	WORKSTATION	10'-10" X 8'-2" / 8'-0"
MS-2	1	MEDIUM METAL SHELF	12.5" X 37" X 52" HT	D-5	1	DESK	30" X 73.5" X 29" HT	MF-2	1	3 TIER FILE	13" X 36" X 56" HT	PH-1	1	PEN HOLDER	2" X 4" X 4" HT	WS-4	1	WORKSTATION	9'-11" X 8'-2"
MS-3	1	MEDIUM METAL SHELF	17.5" X 37" X 52" HT	D-6	1	DESK	30" X 48" X 26.5"	FAN-1	1	PEDESTAL FAN	15"	SL-1	1	STEP LADDER	17" X 30" BASE X 33" HT	WS-5	2	WORKSTATION	8'-2" X 9'-1" / 7'-10.5"
MS-4	12	TALL METAL SHELF	13" X 36" X 78" HT	D-7	1	DESK	48" X 150" X 29"	TS-1	1	TABLE STAND ON WHEELS	19.5" X 32" X 25.5" HT	MSL-1	1	SMALL MAIL SLOT	17" X 60" X 12" HT	WSM-1	1	WORKSTATION - MAIL	13'-11" X 4'-0"
MR-1	1	LARGE METAL RACK	12" X 37.5" X 84"	WD-1	1	WOOD DESK	30" X 60" X 32" HT	TV-1	1	TV MONITOR	29" X 51"	MSL-2	2	LARGE MAIL SLOT	16" X 38" X 60" HT	SEE NOTE-3 FOR WORKSTATIONS WS-1 THROUGH WS-5 AND WSM-1.			
SR-1	1	SMALL STEEL RACK	19" X 36" X 35" HT	F-1	6	MEDIUM FILE CABINET	18" X 28" X 52" HT	TV-2	1	TV MONITOR	33" X 58"	BD-1	1	BLACK DESK	17" X 60" X 40" HT				
BC-1	1	LARGE BOOKCASE	11" X 44" X 67" HT	F-2	3	TALL FILE CABINET	18.5" X 28" X 57.5" HT	WSH-1	1	WOOD SHELF	18.5" X 22" X 48" HT	DH-1	1	DESK HUTCH	17" X 60" X 8" HT				

**NOTES:**  
1. SUBMIT COMPLETE AND VERIFIED FURNITURE LIST AND PHOTO DOCUMENTATION TO THE ENGINEER PRIOR TO REMOVAL AND STORAGE.  
2. FURNITURE LOCATION SHALL COMPLY WITH ADAAG 404.2.4.1  
3. REFER TO SHEET A-11 FOR TYPICAL DOCUMENTATION OF EA WORKSTATION, WS-1 THRU WS-5 AND WSM-1.

**FINISH / MATERIAL SCHEDULE**

TYPE	DESCRIPTION	COLOR	FINISH / PRODUCT INFO.	MANUFACTURER	REMARKS
PT-1	PAINT - INTERIOR WALLS, CONDUIT DROPS	MATCH: EXISTING ROOM COLOR	SEMI-GLOSS	MNF: SHERWIN WILLIAMS CONTACT: SHARI TSUKAYAMA TEL: (808) 497-2468 EMAIL: shari.sherwin@gmail.com	PROVIDE SUBMITTAL AND SAMPLE PRODUCT DATA FOR ARCHITECT REVIEW PRIOR TO ORDER AND INSTALLATION.
RB-1	RUBBER BASE - COVE BASE	MOLASSES R41ML	ARMSTRONG FLOORING (OR APPROVED EQUAL) - 4" RUBBER BASE	MNF: ARMSTRONG FLOORING CONTACT: SHEILA SURBAN, TRI-WEST TEL: (808) 372-0529 EMAIL: ssurban@trwestltd.com	PROVIDE SUBMITTAL AND SAMPLE PRODUCT DATA FOR ARCHITECT REVIEW PRIOR TO ORDER AND INSTALLATION.
VCT-1	VINYL COMPOSITE TILE PREMIUM EXCELON IMPERIAL TEXTURE	51804 EARTHSTONE GREIGE	ARMSTRONG FLOORING (OR APPROVED EQUAL) 12" X 12" X 1/8" POLISHED, SEE REMARKS	MNF: ARMSTRONG FLOORING CONTACT: SHEILA SURBAN, TRI-WEST TEL: (808) 372-0529 EMAIL: ssurban@trwestltd.com	PROVIDE SUBMITTAL AND SAMPLE PRODUCT DATA FOR ARCHITECT REVIEW PRIOR TO ORDER AND INSTALLATION. FLOOR POLISH S-480 OVER NEW TILE.
RS-1	WINDOW ROLLER SHADES (MANUAL)	STONE, 6080 - WOVEN SHADE 1% OPENNESS FACTOR / TRANSPARENCY	MECHO 5 (OR PRE-APPROVED EQUAL) MANUAL ROLLER SHADE, SINGLE ROLL W/ CHAIN PULL, SIDE MOUNTED HARDWARE WITH MATCHING WOVEN SHADE VALANCE AND CLOSURE PANELS.	MNF: MECHOSHADE OR PRE-APPROVED EQUAL CONTACT: CHARLOTTE IIDA TEL: (808) 587-7053 EMAIL: charlotte.iida@gmail.com	PROVIDE SUBMITTAL AND SAMPLE PRODUCT DATA FOR ARCHITECT REVIEW PRIOR TO ORDER AND INSTALLATION.

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED

REID T. MIZIE  
LICENSED PROFESSIONAL ARCHITECT  
No. 13108  
HAWAII, U.S.A.


STATE OF HAWAII  
DEPARTMENT OF LAND AND NATURAL RESOURCES  
LAND DIVISION

DLNR LAND OFFICE IMPROVEMENTS  
KALANIMOKU BUILDING, ROOM 220


INTERIOR ELEVATIONS  
FINISH MATERIAL, FURNITURE LIST

DESIGNED: RTM  
DRAWN: KH  
CHECKED: RTM  
APPROVED: Carty Chang  
E-signed 2024-04-25 05:45PM HST  
carty.s.chang@hawaii.gov  
State of Hawaii  
Chief Engineer


DESIGNED: RTM	SUBMITTED: [Signature]
DRAWN: KH	DATE: 04/12/24
CHECKED: RTM	SCALE: AS NOTED
APPROVED: Carty Chang E-signed 2024-04-25 05:45PM HST carty.s.chang@hawaii.gov State of Hawaii Chief Engineer	DRAWING NO. <b>A-9</b>




**3** **DETAIL - CORNER POCKET**  
SCALE: 3" = 1'-0"



**2** **DETAIL - WINDOW SHADES, TYP**  
SCALE: 3" = 1'-0"



**4** **DETAIL - WINDOW SHADES, TYP**  
SCALE: 3" = 1'-0"




**1** **DETAIL - FLOORING**  
SCALE: 3" = 1'-0"

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED
STATE OF HAWAII DEPARTMENT OF LAND AND NATURAL RESOURCES LAND DIVISION					
DLNR LAND OFFICE IMPROVEMENTS KALANIMOKU BUILDING, ROOM 220					
DETAILS					
DESIGNED:	RTM	SUBMITTED:			
DRAWN:	KH	DATE:	04/12/24		
CHECKED:	RTM	SCALE:	AS NOTED		
APPROVED:	Carty Chang E-signed 2024-04-25 05:45PM HST carty.s.chang@hawaii.gov State of Hawaii	DRAWING NO.	A-10		
CHIEF ENGINEER	OMIZU Architecture Inc.	CHIEF ENGINEER			



REFER TO SHT A-5 FOR DIMENSIONS.

1 WORKSTATION, TYP. WS-1




CAREFULLY REMOVE, STORE, AND REINSTALL GLASS/ PLASTIC SCREENS ON PARTITIONS AT NO ADDITIONAL COST TO THE STATE.

(E) CONDUIT DROP TO REMAIN, TYP.

REFER TO SHT A-5 FOR DIMENSIONS.


2 WORKSTATION, TYP. WS-2



CAREFULLY REMOVE, STORE, AND REINSTALL GLASS/ PLASTIC SCREENS ON PARTITIONS AT NO ADDITIONAL COST TO THE STATE.

REFER TO SHT A-5 FOR DIMENSIONS.


3 WORKSTATION, TYP. WS-3



CAREFULLY REMOVE, STORE, AND REINSTALL GLASS/ PLASTIC SCREENS ON PARTITIONS AT NO ADDITIONAL COST TO THE STATE.

REFER TO SHT A-5 FOR DIMENSIONS.

4 WORKSTATION, TYP. WS-4



REFER TO SHT A-5 FOR DIMENSIONS.

(E) SURFACE MTD CONDUIT. [PT-1]

CAREFULLY REMOVE, STORE, AND REINSTALL GLASS/ PLASTIC SCREENS ON PARTITIONS AT NO ADDITIONAL COST TO THE STATE.

5 WORKSTATION, TYP. WS-5



(E) UNDER HUTCH, 2 EA IN WORKSTATIONS, TYP.

6 WORKSTATION FURNITURE, TYP.



(E) UNDER HUTCH, 1 EA IN WORKSTATIONS, TYP.

7 WORKSTATION FURNITURE, TYP.



(E) CONDUIT DROP TO REMAIN, TYP.

8 CONDUIT DROP, TYP.



MSL-1

(E) CONDUIT DROP TO REMAIN, TYP.

MSL-2

MSL-2

DH-1

MS-3

BD-1

9 WORKSTATION - MAIL. WSM-1

REVISION NO.	SYM.	DESCRIPTION	SHT./OF	DATE	APPROVED

REID T. MIZIE  
LICENSED PROFESSIONAL ARCHITECT  
No. 13108  
HAWAII, U.S.A.

STATE OF HAWAII  
DEPARTMENT OF LAND AND NATURAL RESOURCES  
LAND DIVISION

DLNR LAND OFFICE IMPROVEMENTS  
KALANIMOKU BUILDING, ROOM 220

PHOTOS

DESIGNED: RTM  
DRAWN: KH  
CHECKED: RTM  
APPROVED: Carty Chang  
E-signed 2024-04-25 05:45PM HST  
carty.s.chang@hawaii.gov  
State of Hawaii  
CHIEF ENGINEER

DESIGNED: RTM	SUBMITTED: [Signature]
DRAWN: KH	DATE: 04/12/24
CHECKED: RTM	SCALE: AS NOTED

This work was prepared by me or under my supervision and construction of the project will be under my observation. Expiration date 04/30/26.

OMIZU Architecture Inc.

DRAWING NO.  
**A-11**