

**Questions and Responses for Solicitation No. B25000574**  
**Lahaina Small Boat Harbor Water Sys. Leak Assessment and Repair**  
**10/08/2024**

1. Sheet C-6 calls for Comfort Station Pressure Testing. Please clarify which proposal item should this work be included.

Bid Item No. 2: Phase 2 Leak Assessment.

2. At the time of work will the area still be closed to the public? Or will the contractor be responsible for traffic control, pedestrian barriers, and other things of this sort?

Yes. Traffic and pedestrian control barriers will not be required.

3. Proposal and specifications indicate there are liquidated damages. Please clarify contract duration.

Contract duration is 90 calendar days, as noted on Page P-1 of the Proposal.

4. Is the contractor responsible for striping restorations? If so, please provide details and quantity for bidding purposes.

No.

5. Is there a geotechnical report for this area available? With the proximity to the ocean is groundwater expected during the installation of Waterlines A and B?

No geotechnical report available. Groundwater is not expected to be encountered for Waterlines A and B.

6. Is the contractor required to install, maintain and remove BMP measures on land or in the ocean?

Contractor is required to install, maintain, and remove landside BMPs throughout the duration of the project. BMP notes have been added to the project plans via Addendum No. 1 dated October 8, 2024. An additional bid line item has been included in the revised Proposal form to include BMPs.

7. Proposal Items 1 and 2 have the same description; "Phase 1 Leak Assessment." For clarity please revise the description to the appropriate proposal items.

A revised bid proposal will be issued via Addendum No. 1 dated October 8, 2024.

8. Waterline B appears to run through a portion of sidewalk. Please provide details for restoration.

If new waterlines cross existing sidewalks, repair sidewalk with 4" thick concrete, 2,500 psi strength, with 6x6x6 welded wire fabric at mid-depth. Provide heavy broom finish.

9. Sheet C-7 highlights Existing 6" DI and cap. Please confirm no work is to be done on the highlighted waterlines on Sheet C-7.

No work to be done.

**10. Please confirm the allowance in Proposal Item 4 can also be utilized for the restorations required to complete the repair.**

Yes.