

Temporary Jobsite Office Trailer Specifications for Solicitation

12' wide x 44' long office trailer with 2 offices and a ½ bathroom

Office Trailer must be NEW with 2 individual offices and a common area contained in a single portable trailer

Prewired for data (with network board installed)

Drywall walls and ceiling

LVP flooring

Standing seam roofing

Vinyl slider windows

Window protection grates

Aluminum modular stair system

6 leveling jacks

HVAC in offices and bullpen

LED lighting

2" ball trailer hitch

Prewired for power 220v and 110v

Pre-plumbed to accept water and exit waste

Delivery and setup on site to 66-1380 Mamalahoa Highway, Kamuela, Hi 96743

Specifications Contact:

Nick Agorastos

nicholas.r.agorastos@hawaii.gov

(808) 974-4226