

State of Hawaii
DEPARTMENT OF LAND AND NATURAL RESOURCES
ENGINEERING DIVISION
1151 Punchbowl Street, Room 221
Honolulu, Hawaii 96813

ADDENDUM NO. 1

TO

Job No. J00CM60A
KAHAKAPAO RECREATIONAL AREA ADA IMPROVEMENTS
Makawao, Maui, Hawaii

June 2, 2016

This addendum as issued shall become part of the Contract Documents for the subject project. The bid documents, plans, and specifications shall be amended as follows:

CONSTRUCTION PLANS

(Drawings have been scanned and are available for download at the HiePRO website.)


1. Drawing G-3:

- DELETE Grading Note 14.

2. Drawing C-11:

- DELETE Detail B/C-11.
- REVISE Note 14 to state the following:
“THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER TO IMPLEMENT AND MAINTAIN APPROPRIATE DUST CONTROL MEASURES, SUCH AS, DUST BARRIERS, WATER SPRINKLING, OR OTHER APPLICABLE PRACTICES AS NOTED IN THE HAWAII DOT “CONSTRUCTION BEST MANAGEMENT PRACTICES FIELD MANUAL” (JANUARY 2008) AND SECTIONS 209 & 620 OF THE “HAWAII STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION” (2005). THE CONTRACTOR SHALL INSPECT FUGITIVE DUST GENERATION AND DUST CONTROL MEASURES DAILY AND COORDINATE WITH THE ENGINEER TO TAKE CORRECTIVE ACTIONS AND MAKE ANY REPAIRS TO THE MEASURES AS NECESSARY. DUST CONTROL MEASURES SHOULD BE APPLIED SEVEN (7) DAYS A WEEK, INCLUDING NON-WORKING DAYS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY FINES AND FEES LEVIED FROM NUISANCES OR PROBLEMS ARISING FROM FUGITIVE DUST ORIGINATING FROM THE PROJECT SITE AND PROJECT WORK.”

Engineering Division



Carty S. Chang
Chief Engineer