

**NANAKULI FLOOD CHANNEL OUTLET REPAIR**  
**WAIANAЕ, OAHU, HAWAII**  
**IFB-26-HHL-010**

Pre-bid Conference and Site Visit  
10:00 a.m., Monday April 27, 2026  
89-185 Farrington Highway  
Waianae, Hawai'i 96792.

1. **Introductions**

- Joshua Takano, Project Manager, DHHL
- Bladimir Gonzalez, Engineer III DHHL

2. **Purpose of Pre-Bid Conference**

- To provide potential bidders with a project overview and job site visit.
- To review procurement requirements and allow potential bidders to ask questions and obtain clarification on the bid documents. A written summary of this pre-bid conference will be issued to all plan holders as an Addendum.
- Requests for clarifications and any questions after this meeting shall be submitted in writing and uploaded on HlePRO no later than 4:00 pm, April 29, 2026, responses to all questions received will be posted on HlePRO no later than 4:00 pm, May 4, 2026.

3. **Scope of Work**

**General**

- All work must be performed in accordance with the Technical Specifications and Plans included in the IFB.
- All work and responsibilities listed on the plans are incidental to the bid proposal and are part of this contract.

**Site Work**

- **Mobilization and Demobilization**  
This includes, but is not limited to, the mobilization, proper disposal of debris generated during construction and demobilization.
- **Erosion and Sediment Control Plan and Traffic Control Plan**  
These include, but are not limited to, the requirement specified in the plan.

**Channel Segment**

- **Install Precast Concrete Channel Lining**

This includes but is not limited to removing debris and providing necessary measures to keep the water back in the channel to receive new concrete precast panels. Provide all required tools and equipment, repair materials, and shoring as necessary. Construct concrete lining wall in a manner that does not impede existing channel flow as much as possible while making all upstream transitions gradual in nature to prevent debris buildup. Installation of the new precast concrete lining panel will include prepping the existing channel, drilling in the rebar into the existing structure, erecting the precast pieces, grouting the joint between the channel floor and the new precast pieces, supplying and installing the stainless steel blades in the precast joints and backfilling the vertical gap between the existing channel wall and the new precast panel vertical face, supplying and installing cast in place cap on the top of the walls. Proper disposal of all construction debris).

- **Install Cast-in-Place Concrete Channel Lining**  
This includes but is not limited to removing debris, prepping the existing channel, and providing necessary measures to receive new cast-in-place concrete lining. Provide all required tools and equipment, repair materials, and shoring as necessary. Construct concrete lining in a manner that does not impede existing channel flow as much as possible while making all upstream transitions gradual in nature to prevent debris buildup. Proper disposal of all construction debris.
- **Install New 6' High Vinyl Coated Chain Link Fence on Both Sides of the Channel**
- **Install 2 New Vinyl Coated Chain Link Gates 6' Wide & 6' High**
- **Provide Rip-Rap/Interlocking Boulders Fill Behind Existing Wall**
- **Remove and Replace Existing Pedestrian Bridge and Railing**

#### **4. Procurement reminders**

- This project is not tax exempt. Your bid proposal must be inclusive of General Excise Tax.
- This project is subject to Chapter 104 HRS, Department of Labor and Industrial Relations (DLIR) prevailing wages and salaries. Please note that Wage Rate Bulletin No. 508 can be found in the IFB attachments.
- After offer is due and prior to award of the contract, the Department shall verify compliance with Sections 103D-310 and 103D-328 HRS via Hawaii Compliance Express (HCE) for

the bidder and all subcontractors. Therefore, the bidder and all subcontractors are encouraged to register with HCE. Instructions for registration are at the HCE website:

<http://vendors.ehawaii.gov>.

- Failure by the bidder and/or any subcontractor to rectify a non-compliant status on HCE within ten business days of notification will be considered as sufficient for the disqualification of the bidder and rejection of its proposal.
- Bid security is required for this solicitation.
- The Bid Offer Form in the IFB shall be uploaded to HlePRO as an attachment when submitting a bid. The winning bidder must mail in the original signed Bid Offer Form at the time of the award.

5. Completion Schedule and Liquidated Damages

- Time to complete: 270 Calendar Days from Notice to Proceed
- Liquidated damages: \$1,000.00 per day.

6. Questions/Answers issued by Addenda

- All questions shall be asked via HlePRO in writing by 4:00 pm April 29, 2026
- The answers to those questions will be answered via HlePRO by 4:00 pm May 4, 2026

7. Deadlines

- See attached Submittals and Deadlines Table.

8. Questions and Answers

**NANAKULI FLOOD CHANNEL OUTLET REPAIR**  
**WAIANAЕ, OAHU, HAWAII**  
**IFB-26-HHL-010**

**Submittals and Deadlines Table**

SUBMITTAL	DEADLINE
Questions due on HlePRO	4:00 pm, April 29, 2026
Responses to questions released	4:00 pm, May 4, 2026
Notice of Intention to Bid	2:00 pm, May 8, 2026
Standard Qualification Questionnaire <ul style="list-style-type: none"> <li>• SQQ submittals are to be uploaded on HlePRO with the bid offer form</li> </ul>	3:30 pm, May 8, 2026
Bid Opening <ul style="list-style-type: none"> <li>• Bid offer form shall be uploaded on HlePRO</li> </ul>	2:00 pm, May 20, 2026
Award of contract will be made to the lowest responsible and responsive “Total Sum Bid”, approximately two weeks following bid opening and after certification of the bid tabulation.	