

State of Hawai'i
DEPARTMENT OF AGRICULTURE & BIOSECURITY
1428 South King Street
Honolulu, Hawai'i

ADDENDUM NO. 1

TO

IFB 26-020-ARMD
O'ahu Miscellaneous On-Call Services
Island of O'ahu, Hawai'i

May 13, 2026

The items listed hereinafter are hereby made a part of the contract for the above project and shall govern the work, taking precedence over previously issued Invitation for Bids governing the items mentioned.

GENERAL

Meter Lateral Installation – For bidding purposes, assume the following:

- The laterals will be installed with three feet of cover.
- Pavement consist of 2-inches asphaltic concrete, 4-inches aggregate base course, and 6-inches select borrow subbase.

Tree Removal – For bidding purposes, assume the following:

- Trees are accessible via paved roads.
- Trees are not within the vicinity of overhead electrical wires.
- Trees are to be cut 12-inches above ground.
- Tree root balls are to remain.
- Trees are to be cut into five (5) to ten (10) foot sections and left onsite.

QUESTIONS/RESPONSES FOR SOLICITATION: B26002533 OAHU
MISCELLANEOUS ON-CALL SERVICES

See attached for responses to questions received on 05/07/2026.

DEPARTMENT OF AGRICULTURE & BIOSECURITY



BRIAN KAU, P.E.

Administrator and Chief Engineer
Agricultural Resource Management Division

ADDENDUM NO. 1
IFB 26-020-ARMD
O'ahu Miscellaneous On-Call Services
Island of O'ahu, Hawai'i

**Questions for solicitation B26002533 O‘ahu Miscellaneous On-Call Services
received on 05/07/2026**

1. How much days are set for completing this project?

Location of laterals, tree removal, and/or any other items of work shown in the Special Provisions Scope are unknown at this time. The term of the contract is 730 calendar days from the Notice To Proceed date issued by Department of Agriculture and Biosecurity.

2. Can we schedule a site visit with your team for both Kahuku and Waimanalo sites before the bid due date? It would help us prepare a more accurate bid.

No, there is no pre-bid conference or site visit planned. Location of laterals, tree removal, and/or any other items of work shown in the Special Provisions Scope are unknown at this time. Maps of the Waimanalo and Kahuku Irrigation Systems were provided in the invitation for bids.

3. Please clarify if the contractor is responsible to obtain all trenching permits, street usage permits from C&C for the new lateral installations?

Yes, per Note #5 of the Typical Detail Condition, "THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND/OR APPROVALS PRIOR TO START OF WORK."

4. Line Item 4, Line Item 5, Line Item 6 involving cutting and removing Various diameter Albizia trees. Where are these Albizia trees located?

Location of laterals, tree removal, and/or any other items of work shown in the Special Provisions Scope are unknown at this time. For bidding purposes, assume tree removal work is along the north side of the Waimanalo Reservoir shown in the Waimanalo Irrigation System Map. For bidding purposes, assume trees will be cut into five (5) to ten (10) foot sections and left onsite. Also assume the tree stumps are to be cut 12-inches above ground and that the root-balls are to remain.

5. SP-1 Scope “Removal of sediment and debris from ditches, flumes, culverts in the Waimanalo District.” Can machinery be used to remove the sediment and debris from the ditches, flumes and culverts? If not, then please verify if hand removal is the only method of removal.

Location of laterals, tree removal, and/or any other items of work shown in the Special Provisions Scope are unknown at this time. If the location is accessible, machinery can be used. However, if located in a remote location, hand removal may be the only option.