

**Questions for solicitation: B26002636 Roadway and Parking Lot
Resurfacing and Restriping
05/15/2026**

1. Will a proposal schedule be released for this project?

Start date TBD once PO is issued. Contractor is responsible for confirming with DLNR and B+K on proposed construction start date before scheduling.

2. Are there plans for this project?

No plans available, layout to be similar to existing, stripping to be like for like.

3. Confirm Porta Potty will need to be placed OUTSIDE the entrance gate and BMPs will be needed to secure it

Yes, porta-potty to be placed outside of the main gates.

4. Confirm Vegetation control - 3 ft crusher rock, rolled, tapered down from Asphalt edges - Crusher rock near bottom stops at existing curbs

Yes, this is confirmed for shoulder work.

5. Existing asphalt curbs at key locations will be removed and replaced with new

Yes, plan on removing existing asphalt curbs and installing new ones.

6. Confirm needing COI to add DHHL/County and any others

Yes, please include the DHHL and Maui County as additionally insured under your COI.

7. Are there noise permit requirements

As per Hawai'i DOH Noise Permits and Variances, the contractor will need to obtain a Class A Community Noise Permit for the paving/construction activities associated with the project.

8. Confirm parking lot stoppers are not being replaced.

As per District Superintendent, stoppers are to be removed and left on the side for them to take away.

9. Clarification on saw cut near top sidewalk to be squared to allow for clean Asphalt joint

Yes, the saw cut should be squared off to allow a clean asphalt joint meeting up to the sidewalk.

10. In the SOW, it was called out to use high-durability striping paint, please specify if we're to include the cost of Thermoplastic material.

YES, CONTRACTOR TO INCLUDE COST OF THERMOPLASTIC PAVEMENT MARKING MATERIAL.