STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS

ADDENDUM NO. 2
FOR
KAMEHAMEHA HIGHWAY, WETLAND ENHANCEMENT AT JAMES CAMPBELL NATIONAL WILDLIFE REFUGE
DISTRICT OF KOOLAULOA, ISLAND OF OAHU
FEDERAL-AID PROJECT NO. STP-083-1(085)

November 17, 2026

This Addendum shall make the following amendment(s) to the Solicitation:

A. TABLE OF CONTENTS

1. Delete **TABLE OF CONTENTS,** dated 11/18/24 in its entirety, and replace it with the attached **TABLE OF CONTENTS,** dated r11/17/26.

B. SPECIAL PROVISIONS

1. Delete **SECTION 105 – CONTROL OF WORK,** dated 09/26/22 in its entirety, and replace it with the attached **SECTION 105 – CONTROL OF WORK,** dated r11/17/26.

C. FEDERAL WAGE RATES

1. Delete **FEDERAL WAGE RATES**, dated 05/27/2026 in its entirety, and replace it with the attached **FEDERAL WAGE RATES**, dated 10/15/2026.

D. PROPOSAL SCHEDULE

1. Delete **PROPOSAL SCHEDULE,** dated 09/28/18 in its entirety, and replace it with the attached **PROPOSAL SCHEDULE,** dated r11/17/26.

The following is provided for information.

E. PRE-BID MEETING MINUTES

1. The attached **PRE-BID MEETING MINUTES** are provided for information.

F. RESPONSE TO REQUESTS FOR INFORMATION (QUESTIONS)

1. No **REQUEST FOR INFORMATION QUESTIONS** was received by the October 28, 2026, deadline.

Please acknowledge receipt of this **ADDENDUM NO. 2** by recording the date of its receipt in the space provided on **PAGE P-4** of the Proposal.

Henry Kennedy

HENRY KENNEDY
Engineering Program Manager

TABLE OF CONTENTS

Instructions for Contractor's Licensing

Civil Rights Compliance and Disadvantaged Business Enterprise Special Provisions

Required Federal-Aid Contract Provisions

Special Provisions Title Page

Special Provisions:

DIVISION 100 - GENERAL PROVISIONS		
Section	**Description**	**Pages**
101	Terms, Abbreviations, and Definitions	101-1a – 101-13a
102	Bidding Requirements and Conditions	102-1a – 102-8a
103	Award And Execution of Contract	103-1a – 103-5a
104	Scope of Work	104-1a – 104-2a
105	Control of Work	105-1a – 105-3a
107	Legal Relations and Responsibility To Public	107-1a – 107-7a
108	Prosecution And Progress	108-1a – 108-25a
109	Measurement and Payment	109-1a – 109-2a

DIVISION 200 - EARTHWORK		
Section	**Description**	**Pages**
201	Clearing and Grubbing	201-1a – 201-2a
209	Temporary Water Pollution, Dust, and Erosion Control	209-1a – 209-30a

DIVISION 600 - INCIDENTAL CONSTRUCTION		
Section	**Description**	**Pages**
619	Planting	619-1a – 619-2a
642	Landscape Maintenance	642-1a – 642-4a
699	Mobilization	699-1a

Requirement of Chapter 104, HRS
Wages and Hours of Employees on Public Works Law

Federal Wage Rates

Proposal Title Page

Proposal .....P-1 – P-7
Proposal Schedule .....P-8 – P-10

Surety Bid Bond

Sample Forms

Contract

Performance Bond (Surety)

Performance Bond

Labor and Material Payment Bond (Surety)

Labor and Material Payment Bond

Disclosure of Lobbying Activities
Standard Form - LLL and LLL-A

Statement of Compliance
Form WH-348

Chapter 104, HRS Compliance Certificate

END OF TABLE OF CONTENTS

SECTION 105 – CONTROL OF WORK

Make the following amendments to said Section:

(I) Amend **105.01 – Authority** to read as follows:

"**105.01 Authority.**

(A) Authority of the Engineer. The Engineer is the representative of the Director and has all the authority of the Director with respect to the contract. The Engineer will make decisions on all questions that may arise regarding the contract, such as, but not limited to:

(1) Interpretation of the contract documents.

(2) Acceptability of the materials furnished and work performed.

(3) Manner of performance and rate of progress of the work.

(4) Acceptable fulfillment of the contract on the part of the Contractor.

(5) Compensation under the contract.

The Engineer's decisions on questions, claims, and disputes will be final and conclusive subject to Subsection 107.15 – Disputes and Claims.

The Engineer may delegate specific authority to act for the Engineer to a specific person or persons. Such delegation of authority shall be established in writing and shall become effective upon delivery to the Contractor.

(B) Authority of the Inspectors. Inspectors, as a representative of the Engineer or other agencies, will inspect the work done and materials furnished. Such inspection may extend to the preparation, fabrication or manufacture of the materials to be used. The Inspector does not have authority vested in the Engineer unless specifically delegated in writing. The Inspector may not alter or waive the provisions of the contract, issue instructions contrary to the contract, or act as agent or representative of the Contractor.

Failure of an Inspector at any time to reject non-conforming work shall not be considered a waiver of the State's right to require work in strict conformity with the contract documents as a condition of final acceptance.

(C) Authority of the Consultant and Construction Management. The State may engage consultants and construction managements to perform duties in connection with the work. Unless otherwise specified in writing to the Contractor, such retained consultants and construction managements shall have no greater authority than an Inspector."

(II) Amend **Subsection 105.02 - Submittals** by revising the first paragraph from lines 52 to 61 to read as follows:

"**105.02 Submittals.** The contract contains the description of various items that the Contractor must submit to the Engineer for review and acceptance. The Contractor shall review all submittals for correctness, conformance with the requirements of the contract documents and completeness before submitting them to the Engineer. The submittal shall indicate the contract items and specifications subsections for which the submittal is provided. The submittal shall be legible and clearly indicate what portion of the submittal is being submitted for review. The Contractor shall provide six copies of the required submissions at the earliest possible date."

(III) Amend **Subsection 105.08 (A) - Furnishing Drawings and Special Provisions** to read as follows:

"**(A) Furnishing Drawings and Special Provisions.** The State will furnish the Contractor an electronic set of the special provisions and plans." The Contractor shall have and maintain at least one set of plans and specifications on the work site, at all times."

(IV) Amend **Subsection 105.14(D) – No Designated Storage Area** from lines 421 to 432 to read as follows:

"**(D) No Designated Storage Area.** If no storage area is designated within the contract documents, materials and equipment may be stored anywhere within the State highway right-of-way, provided such storage and access to and from such site, within the sole discretion of the Engineer, does not create a public or traffic hazard or an impediment to the movement of traffic."

(VI) Amend **Subsection 105.16(B) – Substituting Subcontractors** from line 487 to line 494 to read:

"**(B) Substituting Subcontractors.** Under HRS Chapter 103D-302, the Contractor is required to list the names of persons or firms to be engaged by the Contractor as a subcontractor or joint contractor in the performance of the contract. No subcontractor may be added or deleted, unless authorized by the Engineer. Substitutions will be allowed only if the subcontractor:

END OF SECTION 105

"General Decision Number: HI20260001 10/15/2026

State: Hawaii

Construction Types: Building, Heavy, Highway and Residential

Counties: Hawaii Counties of
Hawaii, Honolulu, Kalawao, Kauai and
Maui

BUILDING CONSTRUCTION PROJECTS

RESIDENTIAL CONSTRUCTION PROJECTS (consisting of single family homes and apartments up to and including 4 stories)

HIGHWAY CONSTRUCTION PROJECTS

HEAVY CONSTRUCTION PROJECTS

Modification Number	Publication Date
1	01/16/2026
2	05/18/2026
3	05/27/2026
4	10/15/2026

ASBE0132-001 09/07/2025

	Rates	Fringes
ASBESTOS WORKERS/INSULATOR (INCLUDES APPLICATION OF ALL INSULATING MATERIALS, PROTECTIVE COVERINGS, COATINGS AND FINISHES TO ALL TYPES OF MECHANICAL SYSTEMS. ALSO THE APPLICATION OF FIRESTOPPING MATERIAL FOR WALL OPENINGS AND PENETRATIONS IN WALLS, FLOORS, CEILINGS AND CURTAIN WALLS.)	$ 46.90	29.75

BOIL0627-005 01/01/2025

	Rates	Fringes
BOILERMAKER	$ 49.37	31.25

BRHI0001-001 09/05/2023

	Rates	Fringes
BRICKLAYERS AND STONEMASONS	$ 48.03	32.23
BRICKLAYER: POINTERS, CAULKERS AND WEATHERPROOFERS	$ 48.28	32.23

BRHI0001-002 09/05/2023

	Rates	Fringes
TILE, MARBLE & TERRAZZO WORKER (TILE, MARBLE AND TERRAZZO WORKERS)	$ 46.50	33.00
TILE, MARBLE & TERRAZZO WORKER (TERRAZZO FLOOR GRINDERS AND TENDERS)	$ 43.14	33.00
TILE, MARBLE & TERRAZZO WORKER (TERRAZZO BASE GRINDERS)	$ 44.69	33.00

CARP0745-001 09/01/2025

	Rates	Fringes
CARPENTERS: POWER SAW OPERATORS (2 H.P. AND OVER)	$ 55.65	29.81
CARPENTERS: MILLWRIGHTS AND MACHINE ERECTORS	$ 55.75	29.81
CARPENTERS: (CARPENTERS; HARDWOOD FLOOR LAYERS; PATENT SCAFFOLD ERECTORS (14 FT. AND OVER); PILEDRIVERS; PNEUMATIC NAILERS; WOOD SHINGLERS AND TRANSIT AND/OR LAYOUT MAN)	$ 55.50	29.81

CARP0745-002 09/01/2025

	Rates	Fringes
DRYWALL AND ACOUSTICAL WORKERS AND LATHERS	$ 55.75	29.81

ELEC1186-001 08/24/2025

	Rates	Fringes
ELECTRICIANS: TELECOMMUNICATION WORKER	$ 41.00	16.28
ELECTRICIANS: CABLE SPLICERS	$ 63.90	33.38
ELECTRICIANS	$ 56.55	33.16

ELEC1186-002 08/24/2025

	Rates	Fringes
LINE CONSTRUCTION: TELECOMMUNICATION WORKER	$ 41.00	16.28
LINE CONSTRUCTION: LINEMEN	$ 56.55	33.16
LINE CONSTRUCTION: HEAVY EQUIPMENT OPERATORS	$ 50.90	30.75
LINE CONSTRUCTION: GROUNDMEN/TRUCK DRIVERS	$ 42.41	27.14
LINE CONSTRUCTION: CABLE SPLICERS	$ 63.90	33.38

ELEV0126-001 01/01/2025

	Rates	Fringes
ELEVATOR MECHANIC A. VACATION: EMPLOYER CONTRIBUTES 8% OF BASIC HOURLY RATE FOR 5 YEARS SERVICE AND 6% OF BASIC HOURLY RATE FOR 6 MONTHS TO 5 YEARS SERVICE AS VACATION PAY CREDIT. B. PAID HOLIDAYS: NEW YEAR'S DAY, MEMORIAL DAY, INDEPENDENCE DAY, LABOR DAY, VETERANS' DAY, THANKSGIVING DAY, THE FRIDAY AFTER THANKSGIVING DAY AND CHRISTMAS DAY	$ 73.85	38.44

ENGI0003-002 09/01/2025

	Rates	Fringes
STAND-BY DIVER: OTHER THAN AQUA LUNG	$ 62.97	35.68
STAND-BY DIVER: (AQUA LUNG) (SCUBA)	$ 62.97	35.68
POWER EQUIPMENT OPERATORS:, GROUP 13E: END DUMPS, UNLICENSED (EUCLID, MACK, CATERPILLAR OR SIMILAR); TRACTOR TRAILER (HAULING EQUIPMENT); TANDEM TRUCKS HOOKED UP TO TRAILER (HAULING EQUIPMENT)	$ 59.60	35.68
POWER EQUIPMENT OPERATORS:, GROUP 13D: TRUCK DRIVER (SLIP-IN OR PUP)	$ 59.49	35.68
POWER EQUIPMENT OPERATORS:, GROUP 13C: TRUCK DRIVER (SEMI-TRAILER. ROCK CANS, SEMI-DUMP OR ROLL-OFFS)	$ 59.17	35.68
POWER EQUIPMENT OPERATORS:, GROUP 13B: WATER TRUCK (OVER 2,000 GALLONS); TANDEM DUMP TRUCK, OVER 8 CU. YDS. (WATER LEVEL)	$ 58.52	35.68
POWER EQUIPMENT OPERATORS:, GROUP 13A: DUMP TRUCK, 8 CU.YDS. AND UNDER (WATER LEVEL); WATER TRUCK (UP TO AND INCLUDING 2,000 GALLONS)	$ 58.21	35.68
POWER EQUIPMENT OPERATORS:, GROUP 13: TRUCK DRIVER (UTILITY, FLATBED, ETC.)	$ 57.94	35.68
POWER EQUIPMENT OPERATORS:, GROUP 12A: DOZER (D-11 OR SIMILAR OR LARGER); HYDRAULIC EXCAVATORS (OVER 4 CU. YDS.); LIFTING CRANES (50 TONS AND OVER); PIONEERING DOZER/BACKHOE (INITIAL CLEARING AND EXCAVATION FOR THE PURPOSE OF PROVIDING ACCESS FOR OTHER EQUIPMENT WHERE THE TERRAIN WORKED INVOLVES 1-TO-1 SLOPES THAT ARE 50 FEET IN HEIGHT OR DEPTH, THE SCOPE OF THIS WORK DOES NOT INCLUDE NORMAL CLEARING AND GRUBBING ON USUAL HILLY TERRAIN NOR THE EXCAVATION WORK ONCE THE ACCESS IS PROVIDED); POWER BLADE OPERATOR (CAT 12 OR EQUIVALENT OR OVER); STRADDLE LIFTS (OVER 50 TONS); TOWER CRANE, MOBILE; TRAVELING TRUSS CRANES; UNIVERSAL, LIEBHER, LINDEN, AND SIMILAR TYPES OF TOWER CRANES (IN THE ERECTION, DISMANTLING, AND MOVING OF EQUIPMENT THERE SHALL BE AN ADDITIONAL OPERATING ENGINEER OR HEAVY DUTY REPAIRMAN); YO-YO CAT OR DOZER. BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A		

CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 61.02 35.68

POWER EQUIPMENT OPERATORS:, GROUP 12 CLAMSHELL OR DIPPER OPERATOR; DERRICKS; DRILL RIGS; MULTI-PROPULSION EARTHMOVING MACHINES (2 OR MORE SCRAPERS) (OVER 35 CU. YDS ""STRUCK""M.R.C.); OPERATORS (DERRICKS, PILEDRIVERS AND CRANES); POWER SHOVELS AND DRAGLINES (7 CU. YDS. M.R.C. AND OVER); SELF-PROPELLED RUBBER-TIRED EARTHMOVING EQUIPMENT (OVER 31 CU. YDS.) (657B AND SIMILAR); WHEEL EXCAVATOR (UP TO AND INCLUDING 750 CU. YDS. PER HOUR); WHEEL EXCAVATOR (OVER 750 CU. YDS. PER HOUR). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 60.66 35.68

POWER EQUIPMENT OPERATORS:, GROUP 11: AUTOMATIC SLIP FORM PAVER (CONCRETE OR ASPHALT); BAND WAGON (IN CONJUNCTION WITH WHEEL EXCAVATOR); CABLE-OPERATED CRAWLER CRANES (OVER 25 TONS BUT LESS THAN 50 TONS); CABLE-OPERATED POWER SHOVEL, CLAMSHELL, DRAGLINE AND BACKHOE (OVER 1 CU. YD. UP TO 7 CU. YDS.); GRADALL (OVER 1 CU. YDS. UP TO 7 CU. YDS.); DW-10, 20, ETC. (TANDEM); EARTHMOVING MACHINES (MULTIPLE PROPULSION POWER UNITS AND 2 OR MORE SCRAPERS) (UP TO AND INCLUDING 35 CU. YDS.,"" STRUCK"" M.R.C.); HIGHLINE CABLEWAY; HYDRAULIC BACKHOE (OVER 2 CU. YDS. UP TO AND INCLUDING 4 CU. YDS.); LEVERMAN; LIFT SLAB MACHINE; LOADER (OVER 12 CU. YDS); MASTER BOAT OPERATOR; MOBILE TRUCK CRANE OPERATOR (OVER 25 TONS BUT LESS THAN 50 TONS); (MOBILE TRUCK CRANE DRIVER REQUIRED); PRE-STRESS WIRE WRAPPING MACHINE; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE (CENTER MOUNT) (OVER 25 TONS M.R.C); SELF-PROPELLED COMPACTOR (WITH MULTIPLE-PROPULSION POWER UNITS); SINGLE ENGINE RUBBER TIRED

EARTHMOVING MACHINE (WITH TANDEM SCRAPER); TANDEM CATS; TRENCHER (PULLING ATTACHED SHIELD). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 60.30 35.68

POWER EQUIPMENT OPERATORS:, GROUP 10A: BOAT OPERATOR; CABLE-OPERATED CRAWLER CRANE (UP TO AND INCLUDING 25 TONS); CABLE-OPERATED POWER SHOVEL, CLAMSHELL, DRAGLINE AND BACKHOE (UP TO AND INCLUDING 1 CU. YD.); DOZER D9-L; DOZER (D-10, HD41 AND SIMILAR) (ALL ATTACHMENTS); GRADALL (UP TO AND INCLUDING 1 CU. YD.); HYDRAULIC BACKHOE (OVER 3/4 CU. YDS. UP TO AND INCLUDING 2 CU. YDS.); MOBILE TRUCK CRANE OPERATOR (UP TO AND INCLUDING 25 TONS) (MOBILE TRUCK CRANE DRIVER REQUIRED); SELF-PROPELLED BOOM TYPE LIFTING DEVICE (CENTER MOUNT) (UP TO AND INCLUDING 25 TONS) (GROVE, DROTT, P&H, PETTIBONE AND SIMILAR; TRENCHER (OVER 6 FEET AND 750 H.P. OR MORE); WATCH ENGINEER (STEAM OR ELECTRIC). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 60.15 35.68

POWER EQUIPMENT OPERATORS:, GROUP 10: CHICAGO BOOM; COLD PLANERS; HEAVY DUTY REPAIRMAN OR WELDER; HOIST AND/OR WINCH (3 DRUMS); HYDRAULIC SKOOPER (KOEHRING AND SIMILAR); LOADER (OVER 6 CU. YDS. UP TO AND INCLUDING 12 CU. YDS.); SAURMAN TYPE DRAGLINE (OVER 5 CU. YDS.); SELF-PROPELLED, RUBBER-TIRED EARTHMOVING EQUIPMENT (OVER 20 CU. YDS. UP TO AND INCLUDING 31 CU. YDS.) (637D AND SIMILAR); SOIL STABILIZER (P & H OR EQUAL); SUB-GRADER (GURRIES OR OTHER AUTOMATIC TYPE); TRACTORS (D-9 OR EQUIVALENT, ALL ATTACHMENTS); TRACTOR (TANDEM SCRAPER); WATCH ENGINEER. BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM

OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 60.00 35.68

POWER EQUIPMENT OPERATORS:, GROUP 9A: DOZER (D-8 AND SIMILAR); GRADESETTER (WHEN REQUIRED BY THE CONTRACTOR TO WORK FROM DRAWINGS, PLANS OR SPECIFICATIONS WITHOUT THE DIRECT SUPERVISION OF A FOREMAN OR SUPERINTENDENT); PUSH CAT; SCRAPERS (UP TO AND INCLUDING 20 CU. YDS); SELF-PROPELLED COMPACTOR WITH DOZER; SELF-PROPELLED, RUBBER-TIRED EARTHMOVING EQUIPMENT (UP TO AND INCLUDING 20 CU. YDS) (621 BAND AND SIMILAR); SHEEP'S FOOT; TRACTOR (D-8 AND SIMILAR); TRACTORS WITH BOOM (LARGER THAN D-6, AND SIMILAR). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 59.94 35.68

POWER EQUIPMENT OPERATORS:, GROUP 9: COMBINATION MIXER AND COMPRESSOR (GUNITE); DO-MOR LOADERAND ADAMS ELEGRADER; DOZER (D-7 OR EQUAL); WHEEL AND/OR LADDER TRENCHER (OVER 6 FEET AND 200 TO 749 H.P.). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS

AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO   AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 59.71 35.68

POWER EQUIPMENT OPERATORS:, GROUP 8: ASPHALT PLANT OPERATOR; BARGE MATE (SEAGOING); CAST-IN-PLACE PIPE LAYING MACHINE; CONCRETE BATCH PLANT (MULTIPLE UNITS); CONVEYOR OPERATOR (TUNNEL); DECKMATE; DOZER (D-6 AND SIMILAR); FINISHING MACHINE OPERATOR (AIRPORTS AND HIGHWAYS); GRADESETTER; KOLMAN LOADER (AND SIMILAR); MUCKING MACHINE (CRAWLER-TYPE); MUCKING MACHINE (CONVEYOR-TYPE); NO-JOINT PIPE LAYING MACHINE; PORTABLE CRUSHING AND SCREENING PLANT; POWER BLADE OPERATOR (UNDER 12); SAURMAN TYPE DRAGLINE (UP TO AND INCLUDING 5 YDS.); STATIONARY PIPE WRAPPING, CLEANING AND BENDING MACHINE; SURFACE HEATER AND PLANER OPERATOR, TRACTOR (D-6 AND SIMILAR); TRI-BATCH PAVER; TUNNEL BADGER; TUNNEL MOLE AND/OR BORING MACHINE OPERATOR UNDERBRIDGE PERSONNEL AERIAL PLATFORM (OVER 50 FEET OF PLATFORM). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT   NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT   NOT INCLUDING 130 FEET 0.50 BOOMS AND/OR LEADS OF 130 FEET   UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP   TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO   AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 59.60 35.68

POWER EQUIPMENT OPERATORS:, GROUP 7: CRUSHER PLANT ENGINEER, DOZER (D-4, CASE 450, JOHN DEERE 450, AND SIMILAR); DUAL DRUM MIXER, EXTEND LIFT; HOIST AND/OR WINCH (2 DRUMS); LOADER (OVER 3 AND 1/2 CU. YDS. UP TO AND INCLUDING 6 YARDS.); MECHANICAL FINISHER OR SPREADER MACHINE (ASPHALT), (BARBER GREENE AND SIMILAR) (SCREEDMAN REQUIRED); MINE OR SHAFT HOIST; MOBILE CONCRETE MIXER (OVER 5 TONS); PIPE BENDING MACHINE (PIPELINES ONLY); PIPE CLEANING MACHINE (TRACTOR PROPELLED AND SUPPORTED); PIPE WRAPPING MACHINE (TRACTOR PROPELLED AND SUPPORTED); ROLLER OPERATOR (ASPHALT); SELF-PROPELLED ELEVATING GRADE PLANE; SLUSHER OPERATOR; TRACTOR (WITH BOOM) (D-6, OR SIMILAR); TRENCHER (OVER 6 FEET AND LESS THAN 200 H.P.); WATER TANKER (PULLED BY EUCLIDS, T-PULLS, DW-10, 20 OR 21, OR SIMILAR); WINCHMAN (STERN WINCH ON DREDGE). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT   NOT INCLUDING 130 FEET OR   LEADS OF 100 FEET UP TO BUT   NOT INCLUDING 130 FEET 0.50 BOOMS AND/OR LEADS OF 130 FEET   UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP   TO AND INCLUDING 250 FEET 1.15

BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET

1.75.....$ 59.49 35.68

POWER EQUIPMENT OPERATORS:, GROUP 6: BOOM TRUCK OR DUAL PURPOSE ""A""FRAME TRUCK (OVER 5 TONS); COMBINATION LOADER/BACKHOE (UP TO AND INCLUDING 3/4 CU. YD.); CONCRETE BATCH PLANTS (WET OR DRY); CONCRETE CUTTER, GROOVER AND/OR GRINDER (SELF-PROPELLED UNIT ON STREETS, HIGHWAYS, AIRPORTS, AND CANALS); CONVEYOR OR CONCRETE PUMP (TRUCK OR EQUIPMENT MOUNTED); DRILLING MACHINERY (NOT TO APPLY TO WATERLINERS, WAGON DRILLS OR JACK HAMMERS); FORK LIFT (OVER 10 TONS); LOADER (UP TO AND INCLUDING 3 AND 1/2 CU. YDS); LULL HIGH LIFT (UNDER 40 FEET); LUBRICATION AND SERVICE ENGINEER (MOBILE); MAGINNIS INTERNAL FULL SLAB VIBRATOR (ON AIRPORTS, HIGHWAYS, CANALS AND WAREHOUSES); MAN OR MATERIAL HOIST; MECHANICAL CONCRETE FINISHER (LARGE CLARY, JOHNSON BIDWELL, BRIDGE DECK AND SIMILAR); MOBILE TRUCK CRANE DRIVER; PORTABLE SHOTBLAST CONCRETE CLEANING MACHINE; PORTABLE BORING MACHINE (UNDER STREETS, HIGHWAYS, ETC.); PORTABLE CRUSHER; POWER JUMBO OPERATOR (SETTING SLIP FORMS, ETC., IN TUNNELS); ROLLERS (OVER 5 TONS); SELF-PROPELLED COMPACTOR (SINGLE ENGINE); SELF-PROPELLED PAVEMENT BREAKER; SKIDSTEER LOADER WITH ATTACHMENTS; SLIP FORM PUMPS (POWER DRIVEN BY HYDRAULIC, ELECTRIC, AIR, GAS, ETC., LIFTING DEVICE FOR CONCRETE FORMS); SMALL RUBBER TIRED TRACTORS; TRENCHER (UP TO AND INCLUDING 6 FEET); UNDERBRIDGE PERSONNEL AERIAL PLATFORM (50 FEET OF PLATFORM OR LESS). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET

1.75.....$ 59.17 35.68

POWER EQUIPMENT OPERATORS:, GROUP 5: ASPHALT PLANT FIREMAN; COMPRESSORS, PUMPS, GENERATORS AND WELDING MACHINES (""BANK"" OF 9 OR MORE, INDIVIDUALLY OR COLLECTIVELY); CONCRETE PUMPS OR PUMPCRETE GUNS; LUBRICATION AND SERVICE ENGINEER (GREASE RACK); SCREEDMAN BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET

0.50 BOOMS AND/OR LEADS OF 130 FEET   UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP   TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO   AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 58.52 35.68

POWER EQUIPMENT OPERATORS:, GROUP 4: BOOM TRUCK OR DUAL PURPOSE ""A"" FRAME TRUCK (5 TONS OR LESS); CONCRETE PLACING BOOM (BUILDING CONSTRUCTION); DINKY OPERATOR; ELEVATOR OPERATOR; HOIST AND/OR WINCH (ONE DRUM); STRADDLE TRUCK (ROSS CARRIER, HYSTER AND SIMILAR). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT   NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT   NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET   UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP   TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO   AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 58.21 35.68

POWER EQUIPMENT OPERATORS:, GROUP 3: BRAKEMAN; DECKHAND; FIREMAN; OILER; OILER/GRADECHECKER; SIGNALMAN; SWITCHMAN; HIGHLINE CABLEWAY SIGNALMAN; BARGEMAN; BUNKERMAN; CONCRETE CURING MACHINE (SELF-PROPELLED, AUTOMATICALLY APPLIED UNIT ON STREETS, HIGHWAYS, AIRPORTS AND CANALS); LEVEEMAN; ROLLER (5 TONS AND UNDER); TUGGER HOIST. BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT   NOT INCLUDING 130 FEET OR   LEADS OF 100 FEET UP TO BUT   NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET   UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP   TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO   AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 57.94 35.68

POWER EQUIPMENT OPERATORS:, GROUP 2: CONVEYOR OPERATOR (HANDLING BUILDING MATERIAL); HYDRAULIC MONITOR; MIXER BOX OPERATOR (CONCRETE PLANT). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR

OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 57.77 35.68

POWER EQUIPMENT OPERATORS:, GROUP 1: FORK LIFT (UP TO AND INCLUDING 10 TONS); PARTSMAN (HEAVY DUTY REPAIR SHOP PARTS ROOM WHEN NEEDED). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 57.66 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 12A: DOZER (D-11 OR SIMILAR OR LARGER); HYDRAULIC EXCAVATORS (OVER 4 CU. YDS.); LIFTING CRANES (50 TONS AND OVER); PIONEERING DOZER/BACKHOE (INITIAL CLEARING AND EXCAVATION FOR THE PURPOSE OF PROVIDING ACCESS FOR OTHER EQUIPMENT WHERE THE TERRAIN WORKED INVOLVES 1-TO-1 SLOPES THAT ARE 50 FEET IN HEIGHT OR DEPTH, THE SCOPE OF THIS WORK DOES NOT INCLUDE NORMAL CLEARING AND GRUBBING ON USUAL HILLY TERRAIN NOR THE EXCAVATION WORK ONCE THE ACCESS IS PROVIDED); POWER BLADE OPERATOR (CAT 12 OR EQUIVALENT OR OVER); STRADDLE LIFTS (OVER 50 TONS); TOWER CRANE, MOBILE; TRAVELING TRUSS CRANES; UNIVERSAL, LIEBHER, LINDEN, AND SIMILAR TYPES OF TOWER CRANES (IN THE ERECTION, DISMANTLING, AND MOVING OF EQUIPMENT THERE SHALL BE AN ADDITIONAL OPERATING ENGINEER OR HEAVY DUTY REPAIRMAN); YO-YO CAT OR DOZER. BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING

180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 61.32 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 12: CLAMSHELL OR DIPPER OPERATOR; DERRICKS; DRILL RIGS; MULTI-PROPULSION EARTHMOVING MACHINES (2 OR MORE SCRAPERS) (OVER 35 CU. YDS ""STRUCK""M.R.C.); OPERATORS (DERRICKS, PILEDRIVERS AND CRANES); POWER SHOVELS AND DRAGLINES (7 CU. YDS. M.R.C. AND OVER); SELF-PROPELLED RUBBER-TIRED EARTHMOVING EQUIPMENT (OVER 31 CU. YDS.) (657B AND SIMILAR); WHEEL EXCAVATOR (UP TO AND INCLUDING 750 CU. YDS. PER HOUR); WHEEL EXCAVATOR (OVER 750 CU. YDS. PER HOUR). .....$ 60.96 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 11: AUTOMATIC SLIP FORM PAVER (CONCRETE OR ASPHALT); BAND WAGON (IN CONJUNCTION WITH WHEEL EXCAVATOR); CABLE-OPERATED CRAWLER CRANES (OVER 25 TONS BUT LESS THAN 50 TONS); CABLE-OPERATED POWER SHOVEL, CLAMSHELL, DRAGLINE AND BACKHOE (OVER 1 CU. YD. UP TO 7 CU. YDS.); GRADALL (OVER 1 CU. YDS. UP TO 7 CU. YDS.); DW-10, 20, ETC. (TANDEM); EARTHMOVING MACHINES (MULTIPLE PROPULSION POWER UNITS AND 2 OR MORE SCRAPERS) (UP TO AND INCLUDING 35 CU. YDS.,"" STRUCK"" M.R.C.); HIGHLINE CABLEWAY; HYDRAULIC BACKHOE (OVER 2 CU. YDS. UP TO AND INCLUDING 4 CU. YDS.); LEVERMAN; LIFT SLAB MACHINE; LOADER (OVER 12 CU. YDS); MASTER BOAT OPERATOR; MOBILE TRUCK CRANE OPERATOR (OVER 25 TONS BUT LESS THAN 50 TONS); (MOBILE TRUCK CRANE DRIVER REQUIRED); PRE-STRESS WIRE WRAPPING MACHINE; SELF-PROPELLED BOOM-TYPE LIFTING DEVICE (CENTER MOUNT) (OVER 25 TONS M.R.C); SELF-PROPELLED COMPACTOR (WITH MULTIPLE-PROPULSION POWER UNITS); SINGLE ENGINE RUBBER TIRED EARTHMOVING MACHINE (WITH TANDEM SCRAPER); TANDEM CATS; TRENCHER (PULLING ATTACHED SHIELD). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 60.60 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 10A: BOAT OPERATOR; CABLE-OPERATED CRAWLER CRANE (UP TO AND INCLUDING 25 TONS); CABLE-OPERATED POWER SHOVEL, CLAMSHELL, DRAGLINE AND BACKHOE (UP TO AND INCLUDING 1 CU. YD.); DOZER D9-L; DOZER (D-10, HD41 AND SIMILAR) (ALL ATTACHMENTS); GRADALL (UP TO AND INCLUDING 1 CU. YD.); HYDRAULIC BACKHOE (OVER 3/4

CU. YDS. UP TO AND INCLUDING 2 CU. YDS.); MOBILE TRUCK CRANE OPERATOR (UP TO AND INCLUDING 25 TONS) (MOBILE TRUCK CRANE DRIVER REQUIRED); SELF-PROPELLED BOOM TYPE LIFTING DEVICE (CENTER MOUNT) (UP TO AND INCLUDING 25 TONS) (GROVE, DROTT, P&H, PETTIBONE AND SIMILAR; TRENCHER (OVER 6 FEET AND 750 H.P. OR MORE); WATCH ENGINEER (STEAM OR ELECTRIC). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 60.45 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 10: CHICAGO BOOM; COLD PLANERS; HEAVY DUTY REPAIRMAN OR WELDER; HOIST AND/OR WINCH (3 DRUMS); HYDRAULIC SKOOPER (KOEHRING AND SIMILAR); LOADER (OVER 6 CU. YDS. UP TO AND INCLUDING 12 CU. YDS.); SAURMAN TYPE DRAGLINE (OVER 5 CU. YDS.); SELF-PROPELLED, RUBBER-TIRED EARTHMOVING EQUIPMENT (OVER 20 CU. YDS. UP TO AND INCLUDING 31 CU. YDS.) (637D AND SIMILAR); SOIL STABILIZER (P & H OR EQUAL); SUB-GRADER (GURRIES OR OTHER AUTOMATIC TYPE); TRACTORS (D-9 OR EQUIVALENT, ALL ATTACHMENTS); TRACTOR (TANDEM SCRAPER); WATCH ENGINEER. BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 60.30 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 9A: DOZER (D-8 AND SIMILAR); GRADESETTER (WHEN REQUIRED BY THE CONTRACTOR TO WORK FROM DRAWINGS, PLANS OR SPECIFICATIONS WITHOUT THE DIRECT SUPERVISION OF A FOREMAN OR SUPERINTENDENT); PUSH CAT; SCRAPERS (UP TO AND INCLUDING 20 CU. YDS); SELF-PROPELLED COMPACTOR WITH DOZER; SELF-PROPELLED, RUBBER-TIRED EARTHMOVING EQUIPMENT (UP TO AND INCLUDING 20 CU. YDS) (621 BAND AND SIMILAR); SHEEP'S FOOT; TRACTOR (D-8 AND SIMILAR); TRACTORS WITH BOOM (LARGER THAN

D-6, AND SIMILAR). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET 0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 60.24 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 9: COMBINATION MIXER AND COMPRESSOR (GUNITE); DO-MOR LOADERAND ADAMS ELEGRADER; DOZER (D-7 OR EQUAL); WHEEL AND/OR LADDER TRENCHER (OVER 6 FEET AND 200 TO 749 H.P.). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET 0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 60.01 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 8: ASPHALT PLANT OPERATOR; BARGE MATE (SEAGOING); CAST-IN-PLACE PIPE LAYING MACHINE; CONCRETE BATCH PLANT (MULTIPLE UNITS); CONVEYOR OPERATOR (TUNNEL); DECKMATE; DOZER (D-6 AND SIMILAR); FINISHING MACHINE OPERATOR (AIRPORTS AND HIGHWAYS); GRADESETTER; KOLMAN LOADER (AND SIMILAR); MUCKING MACHINE (CRAWLER-TYPE); MUCKING MACHINE (CONVEYOR-TYPE); NO-JOINT PIPE LAYING MACHINE; PORTABLE CRUSHING AND SCREENING PLANT; POWER BLADE OPERATOR (UNDER 12); SAURMAN TYPE DRAGLINE (UP TO AND INCLUDING 5 YDS.); STATIONARY PIPE WRAPPING, CLEANING AND BENDING MACHINE; SURFACE HEATER AND PLANER OPERATOR, TRACTOR (D-6 AND SIMILAR); TRI-BATCH PAVER; TUNNEL BADGER; TUNNEL MOLE AND/OR BORING MACHINE OPERATOR UNDERBRIDGE PERSONNEL AERIAL PLATFORM (OVER 50 FEET OF PLATFORM). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT

NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 59.90 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 7: CRUSHER PLANT ENGINEER, DOZER (D-4, CASE 450, JOHN DEERE 450, AND SIMILAR); DUAL DRUM MIXER, EXTEND LIFT; HOIST AND/OR WINCH (2 DRUMS); LOADER (OVER 3 AND 1/2 CU. YDS. UP TO AND INCLUDING 6 YARDS.); MECHANICAL FINISHER OR SPREADER MACHINE (ASPHALT), (BARBER GREENE AND SIMILAR) (SCREEDMAN REQUIRED); MINE OR SHAFT HOIST; MOBILE CONCRETE MIXER (OVER 5 TONS); PIPE BENDING MACHINE (PIPELINES ONLY); PIPE CLEANING MACHINE (TRACTOR PROPELLED AND SUPPORTED); PIPE WRAPPING MACHINE (TRACTOR PROPELLED AND SUPPORTED); ROLLER OPERATOR (ASPHALT); SELF-PROPELLED ELEVATING GRADE PLANE; SLUSHER OPERATOR; TRACTOR (WITH BOOM) (D-6, OR SIMILAR); TRENCHER (OVER 6 FEET AND LESS THAN 200 H.P.); WATER TANKER (PULLED BY EUCLIDS, T-PULLS, DW-10, 20 OR 21, OR SIMILAR); WINCHMAN (STERN WINCH ON DREDGE). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15
BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 59.79 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 6: BOOM TRUCK OR DUAL PURPOSE ""A""FRAME TRUCK (OVER 5 TONS); COMBINATION LOADER/BACKHOE (UP TO AND INCLUDING 3/4 CU. YD.); CONCRETE BATCH PLANTS (WET OR DRY); CONCRETE CUTTER, GROOVER AND/OR GRINDER (SELF-PROPELLED UNIT ON STREETS, HIGHWAYS, AIRPORTS, AND CANALS); CONVEYOR OR CONCRETE PUMP (TRUCK OR EQUIPMENT MOUNTED); DRILLING MACHINERY (NOT TO APPLY TO WATERLINERS, WAGON DRILLS OR JACK HAMMERS); FORK LIFT (OVER 10 TONS); LOADER (UP TO AND INCLUDING 3 AND 1/2 CU. YDS); LULL HIGH LIFT (UNDER 40 FEET); LUBRICATION AND SERVICE ENGINEER (MOBILE); MAGINNIS INTERNAL FULL SLAB VIBRATOR (ON AIRPORTS, HIGHWAYS, CANALS AND WAREHOUSES); MAN OR MATERIAL HOIST; MECHANICAL CONCRETE FINISHER (LARGE CLARY, JOHNSON BIDWELL, BRIDGE DECK AND SIMILAR); MOBILE TRUCK CRANE DRIVER; PORTABLE SHOTBLAST CONCRETE CLEANING MACHINE; PORTABLE BORING MACHINE (UNDER STREETS, HIGHWAYS, ETC.); PORTABLE CRUSHER; POWER JUMBO OPERATOR (SETTING SLIP FORMS, ETC., IN

TUNNELS); ROLLERS (OVER 5 TONS); SELF-PROPELLED COMPACTOR (SINGLE ENGINE); SELF-PROPELLED PAVEMENT BREAKER; SKIDSTEER LOADER WITH ATTACHMENTS; SLIP FORM PUMPS (POWER DRIVEN BY HYDRAULIC, ELECTRIC, AIR, GAS, ETC., LIFTING DEVICE FOR CONCRETE FORMS); SMALL RUBBER TIRED TRACTORS; TRENCHER (UP TO AND INCLUDING 6 FEET); UNDERBRIDGE PERSONNEL AERIAL PLATFORM (50 FEET OF PLATFORM OR LESS). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 59.47 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 5: ASPHALT PLANT FIREMAN; COMPRESSORS, PUMPS, GENERATORS AND WELDING MACHINES (""BANK"" OF 9 OR MORE, INDIVIDUALLY OR COLLECTIVELY); CONCRETE PUMPS OR PUMPCRETE GUNS; LUBRICATION AND SERVICE ENGINEER (GREASE RACK); SCREEDMAN. BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET 0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET
1.75.....$ 58.82 35.68

POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 4: BOOM TRUCK OR DUAL PURPOSE ""A"" FRAME TRUCK (5 TONS OR LESS); CONCRETE PLACING BOOM (BUILDING CONSTRUCTION); DINKY OPERATOR; ELEVATOR OPERATOR; HOIST AND/OR WINCH (ONE DRUM); STRADDLE TRUCK (ROSS CARRIER, HYSTER AND SIMILAR BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET 0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING

180 FEET 0.75 BOOMS AND/OR LEADS OF 180
FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER)
WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB)
SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR
WORKED ON SAID CRANE (50 TONS AND OVER) IN
ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF
180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 58.51 35.68
POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 3:
BRAKEMAN; DECKHAND; FIREMAN; OILER;
OILER/GRADECHECKER; SIGNALMAN; SWITCHMAN; HIGHLINE
CABLEWAY SIGNALMAN; BARGEMAN; BUNKERMAN; CONCRETE
CURING MACHINE (SELF-PROPELLED, AUTOMATICALLY
APPLIED UNIT ON STREETS, HIGHWAYS, AIRPORTS AND
CANALS); LEVEEMAN; ROLLER (5 TONS AND UNDER);
TUGGER HOIST. BOOMS AND/OR LEADS (HOURLY
PREMIUMS): THE OPERATOR OF A CRANE (UNDER 50 TONS)
WITH A BOOM OF 80 FEET OR MORE (INCLUDING JIB), OR
OF A CRANE (UNDER 50 TONS) WITH LEADS OF 100 FEET
OR MORE, SHALL RECEIVE A PER HOUR PREMIUM FOR EACH
HOUR WORKED ON SAID CRANE (UNDER 50 TONS) IN
ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF
80 FEET UP TO BUT NOT INCLUDING 130 FEET OR
LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130
FEET 0.50 BOOMS
AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING
180 FEET 0.75 BOOMS AND/OR LEADS OF 180
FEET UP TO AND INCLUDING 250 FEET
1.15 BOOMS AND/OR LEADS OVER 250 FEET
1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER)
WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB)
SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR
WORKED ON SAID CRANE (50 TONS AND OVER) IN
ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF
180 FEET UP TO AND INCLUDING 250 FEET
1.25 BOOMS OVER 250 FEET
1.75.....$ 58.24 35.68
POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 2:
CONVEYOR OPERATOR (HANDLING BUILDING MATERIAL);
HYDRAULIC MONITOR; MIXER BOX OPERATOR (CONCRETE
PLANT). BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE
OPERATOR OF A CRANE (UNDER 50 TONS) WITH A BOOM OF
80 FEET OR MORE (INCLUDING JIB), OR OF A CRANE
(UNDER 50 TONS) WITH LEADS OF 100 FEET OR MORE,
SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR
WORKED ON SAID CRANE (UNDER 50 TONS) IN ACCORDANCE
WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP
TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100
FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130
FEET UP TO BUT NOT INCLUDING 180 FEET
0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND
INCLUDING 250 FEET 1.15
BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE
OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM
OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A
PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE
(50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING
SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING
250 FEET 1.25 BOOMS
OVER 250 FEET
1.75.....$ 58.07 35.68
POWER EQUIPMENT OPERATOR - TUNNEL WORK, GROUP 1:
FORK LIFT (UP TO AND INCLUDING 10 TONS); PARTSMAN
(HEAVY DUTY REPAIR SHOP PARTS ROOM WHEN NEEDED).
BOOMS AND/OR LEADS (HOURLY PREMIUMS): THE OPERATOR
OF A CRANE (UNDER 50 TONS) WITH A BOOM OF 80 FEET
OR MORE (INCLUDING JIB), OR OF A CRANE (UNDER 50
TONS) WITH LEADS OF 100 FEET OR MORE, SHALL RECEIVE
A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID

CRANE (UNDER 50 TONS) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 80 FEET UP TO BUT NOT INCLUDING 130 FEET OR LEADS OF 100 FEET UP TO BUT NOT INCLUDING 130 FEET
0.50 BOOMS AND/OR LEADS OF 130 FEET UP TO BUT NOT INCLUDING 180 FEET 0.75 BOOMS AND/OR LEADS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.15 BOOMS AND/OR LEADS OVER 250 FEET 1.50 THE OPERATOR OF A CRANE (50 TONS AND OVER) WITH A BOOM OF 180 FEET OR MORE (INCLUDING JIB) SHALL RECEIVE A PER HOUR PREMIUM FOR EACH HOUR WORKED ON SAID CRANE (50 TONS AND OVER) IN ACCORDANCE WITH THE FOLLOWING SCHEDULE: BOOMS OF 180 FEET UP TO AND INCLUDING 250 FEET 1.25 BOOMS OVER 250 FEET

1.75	$ 57.96	35.68
HELICOPTER WORK: PILOT OF HELICOPTER	$ 62.83	35.68
HELICOPTER WORK: CO-PILOT OF HELICOPTER	$ 61.66	35.68
HELICOPTER WORK, AIRBORNE HOIST OPERATOR FOR HELICOPTER	$ 61.52	35.68
DIVER: OTHER THAN AQUA LUNG	$ 81.72	35.68
DIVER: (AQUA LUNG) (SCUBA) (up to 30 feet)	$ 72.35	35.68
DIVER: (AQUA LUNG) (SCUBA) (over 30 feet)	$ 81.72	35.68
DIVER TENDER: OTHER THAN AQUA LUNG	$ 59.94	35.68

ENGI0003-004 09/01/2025

	Rates	Fringes
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 7: DECKHAND (CAN OPERATE ANCHOR SCOW UNDER DIRECTION OF DECKMATE); FIREMAN; LEVEEMAN; OILER	$ 57.94	35.68
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 6: WINCHMAN (STERN WINCH ON DREDGE)	$ 59.49	35.68
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 5: DECKMATE.	$ 59.60	35.68
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 4: DOZER OPERATOR.	$ 59.94	35.68
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 3: MECHANIC OR WELDER.	$ 60.00	35.68
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 2: WATCH ENGINEER (STEAM OR ELECTRIC).	$ 60.15	35.68
DREDGING:, HYDRAULIC SUCTION DREDGES: GROUP 1: LEVERMAN.	$ 60.30	35.68
DREDGING:, DERRICKS: GROUP 4: DECKHAND, FIREMAN, OILER	$ 57.94	35.68
DREDGING:, DERRICKS: GROUP 3: DECKMATE; SAURMAN TYPE DRAGLINE (UP TO AND INCLUDING 5 YARDS).	$ 59.60	35.68
DREDGING:, DERRICKS: GROUP 2: SAURMAN TYPE DRAGLINE (OVER 5 CUBIC YARDS).	$ 60.00	35.68
DREDGING:, DERRICKS: GROUP 1: OPERATORS (DERRICKS, PILEDRIVERS AND CRANES).	$ 60.66	35.68
DREDGING:, CLAMSHELL OR DIPPER DREDGING: GROUP 4: BARGEMAN; DECKHAND; FIREMAN; OILER. HYDRAULIC SUCTION DREDGING CLASSIFICATIONS	$ 57.94	35.68
DREDGING:, CLAMSHELL OR DIPPER DREDGING: GROUP 3: BARGE MATE; DECKMATE	$ 59.60	35.68
DREDGING:, CLAMSHELL OR DIPPER DREDGING: GROUP 2: MECHANIC OR WELDER; WATCH ENGINEER	$ 60.00	35.68
DREDGING:, CLAMSHELL OR DIPPER DREDGING: GROUP 1: CLAMSHELL OR DIPPER OPERATOR	$ 60.66	35.68
DREDGING (BOAT OPERATORS): MASTER BOAT OPERATOR	$ 60.30	35.68
DREDGING (BOAT OPERATORS): BOAT OPERATOR	$ 60.15	35.68
DREDGING (BOAT OPERATORS): BOAT DECKHAND	$ 57.94	35.68

ENGI0003-044 09/01/2025

	Rates	Fringes
POWER EQUIPMENT OPERATORS (PAVING): SOIL STABILIZER	$ 59.47	34.86
POWER EQUIPMENT OPERATORS (PAVING): SCREED PERSON	$ 58.64	34.86
POWER EQUIPMENT OPERATORS (PAVING): ROLLER OPERATOR (OVER FIVE TONS)	$ 58.84	34.86
POWER EQUIPMENT OPERATORS (PAVING): ROLLER OPERATOR		

(FIVE TONS AND UNDER).....$ 57.41 34.86
POWER EQUIPMENT OPERATORS (PAVING): LOADER (OVER 2
1/2 CU. YDS. TO AND INCLUDING 5 CU. YDS.).....$ 58.96 34.86
POWER EQUIPMENT OPERATORS (PAVING): LOADER (2 1/2
CU. YDS. AND UNDER).....$ 58.64 34.86
POWER EQUIPMENT OPERATORS (PAVING): LABORER, HAND
ROLLER.....$ 57.18 34.86
POWER EQUIPMENT OPERATORS (PAVING): GRADER.....$ 59.47 34.86
POWER EQUIPMENT OPERATORS (PAVING): CONCRETE SAWS
AND/OR GRINDER (SELF-PROPELLED UNIT ON STREETS,
HIGHWAYS, AIRPORTS AND CANALS).....$ 58.64 34.86
POWER EQUIPMENT OPERATORS (PAVING): COMBINATION
LOADER/BACKHOE (UP TO 3/4 CU.YD.).....$ 56.70 34.86
POWER EQUIPMENT OPERATORS (PAVING): COMBINATION
LOADER/BACKHOE (OVER 3/4 CU.YD.).....$ 57.68 34.86
POWER EQUIPMENT OPERATORS (PAVING): COLD PLANER.....$ 59.47 34.86
POWER EQUIPMENT OPERATORS (PAVING): ASPHALT
SPREADER OPERATOR.....$ 59.16 34.86
POWER EQUIPMENT OPERATORS (PAVING): ASPHALT RAKER...$ 57.68 34.86
POWER EQUIPMENT OPERATORS (PAVING): ASPHALT PLANT
OPERATOR.....$ 59.07 34.86
POWER EQUIPMENT OPERATORS (PAVING): ASPHALT
CONCRETE MATERIAL TRANSFER.....$ 58.67 34.86

IRON0625-001 09/01/2025

Rates Fringes

IRONWORKERS A. EMPLOYEES WILL BE PAID $.50 PER
HOUR MORE WHILE WORKING IN TUNNELS AND COFFER DAMS;
$1.00 PER HOUR MORE WHEN REQUIRED TO WORK UNDER OR
ARE COVERED WITH WATER (SUBMERGED) AND WHEN THEY
ARE REQUIRED TO WORK ON THE SUMMIT OF MAUNA KEA,
MAUNA LOA OR HALEAKALA.....$ 50.50 43.46

LABO0368-001 09/02/2024

Rates Fringes

SEE LABORERS: LABORER II IN FOOTER.....$ 39.15 25.96
SEE LABORERS: LABORER I IN FOOTER.....$ 41.75 25.96
LABORERS: WINDOW WASHER (BOSUN CHAIR).....$ 41.25 25.96
LABORERS: POWDERMAN.....$ 42.75 25.96
LABORERS: MASON TENDER/HOD CARRIER.....$ 42.25 25.96
LABORERS: GUNITE/SHOTCRETE OPERATOR AND HIGH SCALER.$ 42.25 25.96
LABORERS: FINAL CLEAN UP.....$ 31.40 21.37
LABORERS: DRILLER.....$ 44.75 25.96

LABO0368-002 09/03/2024

Rates Fringes

LANDSCAPE & IRRIGATION LABORERS: GROUP 2 LAYOUT OF
IRRIGATION AND OTHER NON-POTABLE IRRIGATION WATER
SYSTEMS AND THE LAYOUT OF DRINKING FOUNTAINS AND
OTHER POTABLE IRRIGATION WATER SYSTEMS IN
CONNECTION WITH SUCH LANDSCAPING AND IRRIGATION
WORK. THIS INCLUDES THE LAYOUT OF ALL HEADS,
RISERS, VALVES, VALVE BOXES, VACUUM BREAKERS, LOW
VOLTAGE ELECTRICAL LINES, HYDRAULIC AND ELECTRICAL
CONTROLLERS, AND METALLIC (COPPERS, BRASS,
GALVANIZED, OR SIMILAR) PIPE, AS WELL AS PVC OR
OTHER PLASTIC PIPE. THIS WORK ALSO INCLUDES THE
READING AND INTERPRETATION OF PLANS AND
SPECIFICATIONS IN CONNECTION WITH THE LAYOUT OF
LANDSCAPING, ROCKSCAPE, WATERSCAPE, AND IRRIGATION
WORK; OPERATION OF HYDRO-MULCHING MACHINES
(SPRAYMAN AND DRIVER), DRILLERS, TRENCHERS (RIDING
TYPE, DAVIS T-66, AND SIMILAR) AND FORK LIFTS USED
IN CONNECTION WITH THE PERFORMANCE OF SUCH
LANDSCAPING AND IRRIGATION WORK; TREE CLIMBERS AND
CHAIN SAW TREE TRIMMERS, SPORADIC OPERATION (WHEN
USED IN CONNECTION WITH LANDSCAPING, ROCKSCAPE,
WATERSCAPE, AND IRRIGATION WORK) OF SKID-STEER
LOADERS (BOBCAT AND SIMILAR), CRANES (BANTAM,
GROVE, AND SIMILAR), HOPTOS, BACKHOES, LOADERS,

ROLLERS, AND DOZERS (CASE, JOHN DEERE, AND SIMILAR), WATER TRUCKS, TRUCKS REQUIRING A STATE OF HAWAII PUBLIC UTILITIES COMMISSION TYPE 5 AND/OR TYPE 7 LICENSE, SIT-DOWN TYPE AND ""GANG"" MOWERS, AND OTHER SELF-PROPELLED, SIT-DOWN OPERATED MACHINES NOT LISTED UNDER LANDSCAPE & IRRIGATION MAINTENANCE LABORER; CHEMICAL SPRAYING USING SELF-PROPELLED POWER SPRAYING EQUIPMENT (200 GALLON CAPACITY OR MORE).....$ 29.40 17.15

LANDSCAPE & IRRIGATION LABORERS,GROUP 2: LAYOUT OF IRRIGATION AND OTHER NON-POTABLE IRRIGATION WATER SYSTEMS AND THE LAYOUT OF DRINKING FOUNTAINS AND OTHER POTABLE IRRIGATION WATER SYSTEMS IN CONNECTION WITH SUCH LANDSCAPING AND IRRIGATION WORK. THIS INCLUDES THE LAYOUT OF ALL HEADS, RISERS, VALVES, VALVE BOXES, VACUUM BREAKERS, LOW VOLTAGE ELECTRICAL LINES, HYDRAULIC AND ELECTRICAL CONTROLLERS, AND METALLIC (COPPERS, BRASS, GALVANIZED, OR SIMILAR) PIPE, AS WELL AS PVC OR OTHER PLASTIC PIPE. THIS WORK ALSO INCLUDES THE READING AND INTERPRETATION OF PLANS AND SPECIFICATIONS IN CONNECTION WITH THE LAYOUT OF LANDSCAPING, ROCKSCAPE, WATERSCAPE, AND IRRIGATION WORK; OPERATION OF HYDRO-MULCHING MACHINES (SPRAYMAN AND DRIVER), DRILLERS, TRENCHERS (RIDING TYPE, DAVIS T-66, AND SIMILAR) AND FORK LIFTS USED IN CONNECTION WITH THE PERFORMANCE OF SUCH LANDSCAPING AND IRRIGATION WORK; TREE CLIMBERS AND CHAIN SAW TREE TRIMMERS, SPORADIC OPERATION (WHEN USED IN CONNECTION WITH LANDSCAPING, ROCKSCAPE, WATERSCAPE, AND IRRIGATION WORK) OF SKID-STEER LOADERS (BOBCAT AND SIMILAR), CRANES (BANTAM, GROVE, AND SIMILAR), HOPTOS, BACKHOES, LOADERS, ROLLERS, AND DOZERS (CASE, JOHN DEERE, AND SIMILAR), WATER TRUCKS, TRUCKS REQUIRING A STATE OF HAWAII PUBLIC UTILITIES COMMISSION TYPE 5 AND/OR TYPE 7 LICENSE, SIT-DOWN TYPE AND ""GANG"" MOWERS, AND OTHER SELF-PROPELLED, SIT-DOWN OPERATED MACHINES NOT LISTED UNDER LANDSCAPE & IRRIGATION MAINTENANCE LABORER; CHEMICAL SPRAYING USING SELF-PROPELLED POWER SPRAYING EQUIPMENT (200 GALLON CAPACITY OR MORE).....$ 29.40 17.15

LANDSCAPE & IRRIGATION LABORERS, GROUP 3: MAINTENANCE OF TREES, SHRUBS, GROUND COVERS, LAWNS AND OTHER PLANTED AREAS, INCLUDING THE REPLANTING OF TREES, SHRUBS, GROUND COVERS, AND OTHER PLANTINGS THAT DID NOT ""TAKE"" OR WHICH ARE DAMAGED; PROVIDED, HOWEVER, THAT RE-PLANTING THAT REQUIRES THE USE OF EQUIPMENT, MACHINERY, OR POWER TOOLS SHALL BE PAID FOR AT THE RATE OF PAY SPECIFIED UNDER LANDSCAPE AND IRRIGATION LABORER, GROUP 1; RAKING, MOWING, TRIMMING, AND RUNING, INCLUDING THE USE OF ""WEED EATERS"", HEDGE TRIMMERS, VACUUMS, BLOWERS, AND OTHER HAND-HELD GAS, AIR, ELECTRIC, OR SELF-POWERED TOOLS, AND THE OPERATION OF LAWN MOWERS (NOTE: THE OPERATION OF SIT-DOWN TYPE AND ""GANG"" MOWERS SHALL BE PAID FOR AT THE RATE OF PAY SPECIFIED UNDER LANDSCAPE & IRRIGATION LABORER, GROUP 2); GUYWIRING, STAKING, PROPPING, AND SUPPORTING TREES; FERTILIZING, CHEMICAL SPRAYING USING SPRAY EQUIPMENT WITH LESS THAN 200 GALLON CAPACITY, MAINTAINING IRRIGATION AND SPRINKLER SYSTEMS, INCLUDING THE STAKING, CLAMPING, AND ADJUSTMENT OF RISERS, AND THE ADJUSTMENT AND/OR REPLACEMENT OF SPRINKLER HEADS, (NOTE: THE CLEANING AND GLUING OF PIPE AND FITTINGS SHALL BE PAID FOR AT THE RATE OF PAY SPECIFIED UNDER LANDSCAPE & IRRIGATION LABORER(GROUP 1); WATERING BY HAND OR SPRINKLER SYSTEM AND THE PEFORMANCE OF OTHER TYPES OF GARDENING, YARDMAN, AND HORTICULTURAL-RELATED WORK.....$ 23.00 17.15

LANDSCAPE & IRRIGATION LABORERS, GROUP 1: INSTALLATION OF NON-POTABLE PERMANENT OR TEMPORARY

IRRIGATION WATER SYSTEMS PERFORMED FOR THE PURPOSES OF LANDSCAPING AND IRRIGATION ARCHITECTURAL HORTICULTURAL WORK; THE INSTALLATION OF DRINKING FOUNTAINS AND PERMANENT OR TEMPORARY IRRIGATION SYSTEMS USING POTABLE WATER FOR LANDSCAPING AND IRRIGATION ARCHITECTURAL HORTICULTURAL PURPOSES ONLY. THIS WORK INCLUDES (A) THE INSTALLATION OF ALL HEADS, RISERS, VALVES, VALVE BOXES, VACUUM BREAKERS (PRESSURE AND NON-PRESSURE), LOW VOLTAGE ELECTRICAL LINES AND, PROVIDED SUCH WORK INVOLVES ELECTRICAL WIRING THAT WILL CARRY 24 VOLTS OR LESS, THE INSTALLATION OF SENSORS, MASTER CONTROL PANELS, DISPLAY BOARDS, JUNCTION BOXES, CONDUCTORS, INCLUDING ALL OTHER COMPONENTS FOR CONTROLLERS, (B) AND METALLIC (COPPER, BRASS, GALVANIZED, OR SIMILAR) PIPE, AS WELL AS PVC OR OTHER PLASTIC PIPE INCLUDING ALL WORK INCIDENTAL THERETO, I.E., UNLOADING, HANDLING AND DISTRIBUTION OF ALL PIPES FITTINGS, TOOLS, MATERIALS AND EQUIPMENT, (C) ALL SOLDERING WORK IN CONNECTION WITH THE ABOVE WHETHER DONE BY TORCH, SOLDERING IRON, OR OTHER MEANS; (D) TIE-IN TO MAIN LINES, THRUST BLOCKS (BOTH PRECAST AND POURED IN PLACE), PIPE HANGERS AND SUPPORTS INCIDENTAL TO INSTALLATION OF THE ENTIRE IRRIGATION SYSTEM, (E) MAKING OF PRESSURE TESTS, START-UP TESTING, FLUSHING, PURGING, WATER BALANCING, PLACING INTO OPERATION ALL IRRIGATION EQUIPMENT, FIXTURES AND APPURTENANCES INSTALLED UNDER THIS AGREEMENT, AND (F) THE FABRICATION, REPLACEMENT, REPAIR AND SERVICING OFLANDSCAPING AND IRRIGATION SYSTEMS. OPERATION OF HAND-HELD GAS, AIR, ELECTRIC, OR SELF-POWERED TOOLS AND EQUIPMENT USED IN THE PERFORMANCE OF LANDSCAPE AND IRRIGATION WORK IN CONNECTION WITH ARCHITECTURAL HORTICULTURE; CHOKE-SETTING, SIGNALING, AND RIGGING FOR EQUIPMENT OPERATORS ON JOB-SITE IN THE PERFORMANCE OF SUCH LANDSCAPING AND IRRIGATION WORK; CONCRETE WORK (WET OR DRY) PERFORMED IN CONNECTION WITH SUCH LANDSCAPING AND IRRIGATION WORK. THIS WORK SHALL ALSO INCLUDE THE SETTING OF ROCK, STONE, OR RIPRAP IN CONNECTION WITH SUCH LANDSCAPE, WATERSCAPE, ROCKSCAPE, AND IRRIGATION WORK; GRUBBING, PICK AND SHOVEL EXCAVATION, AND HAND ROLLING OR TAMPING IN CONNECTION WITH THE PERFORMANCE OF SUCH LANDSCAPING AND IRRIGATION WORK; SPRIGGING, HANDSEEDING, AND PLANTING OF TREES, SHRUBS, GROUND COVERS, AND OTHER PLANTINGS AND THE PERFORMANCE OF ALL TYPES OF GARDENING AND HORTICULTURAL WORK RELATING TO SAID PLANTING; OPERATION OF FLAT BED TRUCKS (UP TO AND INCLUDING 2 1/2 TONS).: .....$ 28.40 17.15

LABO0368-003 09/02/2024

	Rates	Fringes
UNDERGROUND LABORER, GROUP 7: SHIFTER (SHAFT WORK & RAISER).....	$ 46.40	25.91
UNDERGROUND LABORER, GROUP 6: SHIFTER.....	$ 45.95	25.91
UNDERGROUND LABORER, GROUP 5: SHAFT WORK & RAISE (BELOW ACTUAL OR EXCAVATED GROUND LEVEL); DIAMOND DRILLER; GUNITE OR SHOTCRETE NOZZLEMAN; RODMAN; GROUNDMAN.....	$ 45.70	25.91

UNDERGROUND LABORER, GROUP 4: MINERS - TUNNEL (INCLUDING TOP AND BOTTOM MAN ON SHAFT AND RAISE WORK); TIMBERMAN, RETIMBERMAN (WOOD OR STEEL OR SUBSTITUTE MATERIALS THEREOF); BLASTERS, DRILLERS, POWDERMAN (IN HEADING); MICROTUNNEL LABORER; HEADMAN; CHERRY PICKERMAN (WHERE CAR IS LIFTED); NIPPER; GROUT GUNMEN; GROUT PUMPMAN & POTMAN; GUNITE, SHOTCRETE GUNMEN & POTMEN; CONCRETE FINISHER (IN TUNNEL); CONCRETE SCREED MAN; BIT GRINDER; STEEL FORM RAISERS & SETTERS; HIGH PRESSURE NOZZLEMAN; NOZZLEMAN (ON SLICK LINE); SANDBLASTER-POTMAN (COMBINATION WORK ASSIGNMENT

INTERCHANGEABLE); TUGGER.....$ 45.35 25.91
UNDERGROUND LABORER, GROUP 3: CHUCKTENDERS AND
CABLETENDERS; POWDERMAN (PRIME HOUSE); VIBRATORMAN,
PAVEMENT BREAKERS.....$ 44.35 25.91
UNDERGROUND LABORER, GROUP 2: SWAMPER; BRAKEMAN;
BULL GANG-MUCKERS, TRACKMEN; DUMPMEN (ANY METHOD);
CONCRETE CREW (INCLUDES RODDING AND SPREADING);
GROUT CREW; REBOUNDMEN.....$ 43.85 25.91
UNDERGROUND LABORER, GROUP 1: WATCHMEN; CHANGE
HOUSE ATTENDANT.....$ 42.35 25.91

PAIN1791-001 07/01/2025

	Rates	Fringes
PAINTERS: SANDBLASTER; SPRAY	$ 44.05	30.05
PAINTERS: BRUSH	$ 44.05	30.05

PAIN1889-001 07/01/2025

	Rates	Fringes
GLAZIERS	$ 48.50	40.20

PAIN1926-001 03/02/2025

	Rates	Fringes
SOFT FLOOR LAYERS	$ 43.27	35.18

PAIN1944-001 01/01/2025

	Rates	Fringes
TAPER	$ 47.36	32.00

PLAS0630-001 09/04/2023

	Rates	Fringes
PLASTERER	$ 46.12	34.53

PLAS0630-002 09/04/2023

	Rates	Fringes
CEMENT MASONS: TROWEL MACHINE OPERATORS	$ 44.27	33.63
CEMENT MASONS	$ 44.12	33.63

PLUM0675-001 07/06/2025

	Rates	Fringes
PLUMBER, PIPEFITTER, STEAMFITTER & SPRINKLER FITTER	$ 53.83	33.19

ROOF0221-001 09/06/2026

	Rates	Fringes
ROOFERS (INCLUDING BUILT UP, COMPOSITION AND SINGLE PLY)	$ 45.55	23.36

SHEE0293-001 03/02/2025

	Rates	Fringes
SHEET METAL WORKER	$ 50.16	33.32

SUHI1997-002 09/15/1997

	Rates	Fringes
FENCE ERECTOR (CHAIN LINK FENCE)	$ 9.33	1.65
DRAPERY INSTALLER	$ 13.60	1.20

WELDERS - Receive rate prescribed for craft performing
operation to which welding is incidental.
==========
Note: Executive Order (EO) 13706, Establishing Paid Sick Leave
for Federal Contractors applies to all contracts subject to the
Davis-Bacon Act for which the contract is awarded (and any

solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at https://www.dol.gov/agencies/whd/government-contracts.

Note: Executive Order 13658 generally applies to contracts subject to the Davis-Bacon Act that were awarded on or between January 1, 2015 and January 29, 2022, and that have not been renewed or extended on or after January 30, 2022. Executive Order 13658 does not apply to contracts subject only to the Davis-Bacon Related Acts regardless of when they were awarded. If a contract is subject to Executive Order 13658, the contractor must pay all covered workers at least $13.65 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract from May 11, 2026, through December 31, 2026. The applicable Executive Order minimum wage rate will be adjusted annually. Additional information on contractor requirements and worker protections under Executive Order 13658 is available at www.dol.gov/whd/govcontracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than "SU", "UAVG", "SA", or "SC" denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number

used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The "SU" identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

"SU" wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The "SA" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the "SA" identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

a) a survey underlying a wage determination
b) an existing published wage determination
c) an initial WHD letter setting forth a position on a wage determination matter
d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations
Wage and Hour Division
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board
U.S. Department of Labor
200 Constitution Avenue, N.W.
Washington, DC 20210.

==========

END OF GENERAL DECISION"

PROPOSAL SCHEDULE					
ITEM NO.	**ITEM**	**APPROX. QUANTITY**	**UNIT**	**UNIT PRICE**	**AMOUNT**
201.0300	Clearing and Grubbing	LS	LS	LS	$_____
201.0400	Herbicide Application	LS	LS	LS	$_____
209.0200	Installation, Maintenance, Monitoring and Removal of BMP	LS	LS	LS	$_____
619.0500	Groundcover (*Cladium jamaicense*, *Cyperus javanicus*, *Cyperus laevigatus*, *Eleocharis calva*, *Schoenoplectus tabernaemontani* [1-gallon pots for all species])	LS	LS	LS	$_____
642.0300	Plant Maintenance	LS	LS	LS	$_____
642.0400	Monitoring Vegetation Plots and Photo Points	LS	LS	LS	$_____
648.0100	Field-Posted Drawings	LS	LS	LS	$_____
699.0100	Mobilization (Not to Exceed 6 percent of the Sum of All Items Excluding the Bid Price of this Item)	LS	LS	LS	$_____
Total Amount for Comparison of Bids……					$ _____
NOTE: Bidders shall complete all unit prices and amounts. Failure to do so shall be grounds for rejection of bid.					

PROPOSAL SCHEDULE

The bidder is directed to Subsection 105.16 – Subcontracts.

The bidder's attention is directed to Sections 696 - Field Office and Project Site Laboratory and 699 - Mobilization for the limitation of the amount bidders are allowed to bid.

If the bid price for any proposal item having a maximum allowable bid indicated therefore in any of the contract documents is in excess of such a maximum amount, the bid price for such proposal item shall be adjusted to reflect the limitation thereon. The comparison of bids to determine the successful bidder and the amount of contract to be awarded shall be determined after such adjustments are made, and such adjustments shall be binding upon the bidder.

The bidder is directed to Section 717 – Cullet and Cullet-Made Materials regarding recycling of waste glass.

The bidder should also be aware of the following:

1. Bids shall include all Federal, State, County and other applicable taxes and fees.

2. The TOTAL AMOUNT FOR COMPARISON OF BIDS shall be used to determine the lowest responsible bidder.

3. Bidders shall complete all unit prices and amounts. Failure to do so shall be grounds for rejection of bid.

4. If a discrepancy occurs between unit bid price and the bid price, the unit bid price shall govern.

5. **Bidders shall submit and <u>upload the complete proposal to HIePRO</u> prior to the bid opening date and time. Proposals received after said due date and time shall not be considered. Any additional support documents explicitly designated as <u>confidential and/or proprietary</u> shall be uploaded as a <u>separate file</u> to HIePRO. Bidders shall not include confidential and/or proprietary documents with the proposal. The record of each bidder and respective bid shall be open to public inspection.** Original (wet ink, hard copy) proposal documents are not required to be submitted. **Contract award shall be based on evaluation of proposals submitted and uploaded to HIePRO.**

FAILURE TO UPLOAD THE COMPLETE PROPOSAL TO HIePRO SHALL BE GROUNDS FOR REJECTION OF THE BID.

If there is a conflict between the specification document and the HIePRO solicitation, the specifications shall govern and control, unless otherwise specified.

KAMEHAMEHA HIGHWAY, WETLAND ENHANCEMENT AT JAMES CAMPBELL NATIONAL WILDLIFE REFUGE ISLAND OF OAHU

FEDERAL-AID PROJECT NO. STP-083-1(085)

PRE-BID MEETING MINUTES
October 21, 2026

The following notes are from the Hawaii Department of Transportation (HDOT) pre-bid meeting with prospective bidders for the Kamehameha Highway, Wetland Enhancement at James Campbell National Wildlife Refuge, Island of Oahu project.

The meeting was conducted virtually via Microsoft Teams at 2:00 p.m.

All attendees were notified of the following:

- Scope of work consists of removing specified invasive plants, installing restoration plantings of native wetland plants, and conducting follow-up maintenance and monitoring. All work will occur at and near Pond F-Mauka, including a laydown and parking area and the California bulrush composting area, and at a reference site, the Punamano Unit. Both sites are at the James Campbell National Wildlife Refuge near Kahuku on Oahu.

- Proposals are due by November 13, 2026, at 2:00 p.m.

- Request for Information (RFI) questions are due by October 28, 2026, at 2:00 p.m.

- Attendance at this meeting is optional for bidding.

- The solicited drawings and specifications already include all items mentioned at this pre-bid conference. This meeting introduces nothing new. Bidders shall submit any new items in writing as an RFI.

- Unlike previous Federal-Aid projects, this contract has no Disadvantaged Business Enterprise goal. The Office of Civil Rights reviewed the requirements.

- Contract duration is 1,829 calendar days (approximately 5 years) from the Start Work Date set by the Department.

- Per Spec 107, the State will initiate the Contractor's Right-of-Entry to work at James Campbell National Wildlife Refuge soon after contract award, naming the Contractor that will perform the work.

- Pond F-Mauka provides habitat for federally listed endangered waterbirds. The Contractor shall minimize project activities at Pond F-Mauka to the greatest extent possible during the main nesting and fledging season (March through August).

- A biological monitor shall conduct waterbird nest surveys where appropriate habitat occurs within the vicinity of the project site before work begins. The monitor shall repeat surveys within three days of project initiation and after any work delay of three or more days, during which birds may attempt to nest. If the monitor finds an active nest or brood, the reporting and mitigation requirements in the drawing notes apply.

- Per Spec 107.03, working hours are 7:00 a.m. to 3:30 p.m., Monday through Friday, excluding holidays.

- Because the work will occur on U.S. Fish and Wildlife Service property, Spec 107.01 requires the Certificate of Insurance to name the State and the U.S. Fish and Wildlife Service as additional insureds, with an Indemnification Agreement.

- During the first year, USFWS will dewater Pond F-Mauka. Between September and February (the non-breeding season for endangered waterbirds), the Contractor shall excavate the 2.3 acres of California bulrush to a depth of up to 1 foot with an appropriately sized excavator and transport the material to the composting area. The Contractor shall excavate one scoop at a time and load material directly onto trucks for transport. Stockpiling excavated material or grading within the excavated area in Pond F-Mauka is not permitted.

- The Contractor shall use backpack sprayers to treat any California bulrush that reestablishes at the project site.

- The Landscape Contractor shall supply plants in 1-gallon pots or larger, as specified in the plant species selection table. The work includes five native plant species. The Contractor should coordinate with the nursery to collect seeds and grow the plants for planting.

- Planting shall occur between November and February of the contract's second year, outside the endangered waterbird breeding season.

- The Contractor shall prepare maintenance and monitoring reports during the third through fifth years.

Attendance List:
HDOT Highways Division, Design Branch (HWY-DS)
HDOT Office of Civil Rights
HDOT Highways Division, Oahu District (HWY-OR)
SWCA Environmental Consultants
Island Landscape and Maintenance
Hui ku Plants
Ohana Mac Nut Farm LLC and Shine Naturally

The meeting ended at 2:25 p.m.

All items discussed at this meeting are for clarification only. The bid documents shall govern over anything said at the meeting and discrepancies shall be clarified in an Addendum.