

State of Hawaii
DEPARTMENT OF LAND AND NATURAL RESOURCES
ENGINEERING DIVISION
1151 Punchbowl Street, Room 221
Honolulu, Hawaii 96813

ADDENDUM NO. 1

TO

Job No. H87C836D
KEKAHA KAI STATE PARK
MAHAIULA IMPROVEMENTS
North Kona, Island of Hawaii, Hawaii

AUG 17 2016

This addendum as issued shall become part of the Contract Documents for the subject project. The bid documents, plans, and specifications shall be amended as follows:

SPECIFICATION

1. The following sub-paragraph in Section 03300 – CAST-IN-PLACE CONCRETE, 3.13 FIELD QUALITY CONTROL, paragraph “A” has been revised as follows:
“Testing and Inspecting: The Contractor shall engage a special inspector to perform field tests and inspections and prepare test reports at no cost to the State.”
2. Add the following sub-paragraph to Section 15400 - PLUMBING, 2.04 PLUMBING FIXTURES, B. Fixtures List:

“2. Outhouse Toilet Pedestal (OTP-1, Accessible) shall be fiberglass, floor mounted, one-piece construction, white, with gel coated exterior surfaces. Pedestal height shall be 18-inches, with integral bottom flange. Provide with white, solid plastic open front, elongated seat, with cover, and stainless steel check hinges and posts. Seat and pedestal assembled height shall not exceed 19-inches.

<u>Item</u>	<u>Manufacturer</u>	<u>Model</u>	
Toilet Pedestal		Far North Fiberglass	N/A
Seat	Bemis	1950SS”	

CONSTRUCTION PLANS

1. Sheet C-2: Clarification of BBQ pit “refurbishing” definition. “Refurbishing” consists of fixing existing rock facing; no new grills or other accessories required. Contractor shall contact Tracy Tam-Sing prior to removing any rocks from within the park.

2. Sheet C-3: Revision to removal and relocation of two existing palm trees near new BBQ pit. Two existing palm trees near new BBQ pit will be removed only; no relocation needed.
3. Sheet C-3: Revise Joint Notes, No.1 as follows;
“1. Maximum spacing between any two consecutive control joints shall be 5 feet. Control joints shall be placed in the longitudinal and transverse directions on sidewalks, curbs, slabs, and as shown on the plans.”
4. Sheet S-1: The first sentence in Special Inspections note “A” shall be replaced with the following sentence; “The Contractor shall be responsible for ensuring that special inspection of portions of the work as required by the building code is made at the appropriate time at no cost to the State.”
5. Replace all existing toilet pedestals as outlined below.


DEMOLITION NOTES:

1. Remove existing accessible floor mounted outhouse toilet pedestal, toilet seat and appurtenances (Men’s and Women’s Restrooms). Protect in-place existing floor opening and flooring materials.

FIXTURE INSTALLATION NOTES:

1. Install new floor mounted accessible fiberglass outhouse toilet pedestal (OTP-1) and appurtenances at existing floor opening (Men’s and Women’s Restrooms). Secure toilet pedestal to existing flooring in accordance with manufacturer’s recommendations. Provide stainless steel vandal resistant fasteners. Secure toilet seat to new pedestal in accordance with pedestal manufacturer’s recommendations. See revised Section 15400 - PLUMBING, 2.04 PLUMBING FIXTURES, B. Fixtures List for fixture type.

Engineering Division



Carty S. Chang
Chief Engineer